

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAS 429 C.H. 23	94-00087 -00-BR	HANCOCK	43	12
ROAD DIST.	ILLINOIS			

Contract No. 93401
Sheet 6 of 20

☉ ROADWAY & PROFILE GRADE (BEAM 3)

LOCATION	STATION	OFFSET	THEORETICAL GRADE ELEVATIONS	THEORETICAL GRADE ELEVATIONS ADJUSTED FOR DEAD LOAD DEFLECTION
Bk. W. Abut.	31124.125	.000	564.100	564.100
☉ Brg. W. Abut	31127.000	.000	564.100	564.100
A	31137.000	.000	564.100	564.116
B	31147.000	.000	564.100	564.129
C	31157.000	.000	564.100	564.132
D	31167.000	.000	564.100	564.130
E	31177.000	.000	564.100	564.119
F	31187.000	.000	564.100	564.110
☉ Brg. Pier 1	31199.000	.000	564.100	564.100
G	31209.000	.000	564.100	564.111
H	31219.000	.000	564.100	564.122
I	31229.000	.000	564.100	564.131
J	31239.000	.000	564.100	564.140
K	31249.000	.000	564.100	564.140
L	31259.000	.000	564.100	564.131
M	31269.000	.000	564.100	564.122
N	31279.000	.000	564.100	564.111
☉ Brg. Pier 2	31289.000	.000	564.100	564.100
O	31299.000	.000	564.100	564.110
P	31309.000	.000	564.100	564.121
Q	31319.000	.000	564.100	564.130
R	31329.000	.000	564.100	564.138
S	31339.000	.000	564.100	564.138
T	31349.000	.000	564.100	564.130
U	31359.000	.000	564.100	564.121
V	31369.000	.000	564.100	564.110
☉ Brg. Pier 3	31379.000	.000	564.100	564.100
W	31389.000	.000	564.100	564.111
X	31399.000	.000	564.100	564.122
Y	31409.000	.000	564.100	564.131
Z	31419.000	.000	564.100	564.140
AA	31429.000	.000	564.100	564.140
BB	31439.000	.000	564.100	564.131
CC	31449.000	.000	564.100	564.122
DD	31459.000	.000	564.100	564.111
☉ Brg. Pier 4	31469.000	.000	564.100	564.100
EE	31479.000	.000	564.100	564.109
FF	31489.000	.000	564.100	564.117
GG	31499.000	.000	564.100	564.128
HH	31509.000	.000	564.100	564.132
II	31519.000	.000	564.100	564.129
JJ	31529.000	.000	564.100	564.119
☉ Brg. E. Abut.	31541.000	.000	564.100	564.100
Bk. E. Abut.	31543.875	.000	564.100	564.100

BEAM 4

LOCATION	STATION	OFFSET	THEORETICAL GRADE ELEVATIONS	THEORETICAL GRADE ELEVATIONS ADJUSTED FOR DEAD LOAD DEFLECTION
Bk. W. Abut.	31124.125	6.250	564.003	564.003
☉ Brg. W. Abut	31127.000	6.250	564.003	564.003
A	31137.000	6.250	564.003	564.018
B	31147.000	6.250	564.003	564.031
C	31157.000	6.250	564.003	564.034
D	31167.000	6.250	564.003	564.032
E	31177.000	6.250	564.003	564.022
F	31187.000	6.250	564.003	564.013
☉ Brg. Pier 1	31199.000	6.250	564.003	564.003
G	31209.000	6.250	564.003	564.014
H	31219.000	6.250	564.003	564.025
I	31229.000	6.250	564.003	564.034
J	31239.000	6.250	564.003	564.042
K	31249.000	6.250	564.003	564.042
L	31259.000	6.250	564.003	564.034
M	31269.000	6.250	564.003	564.024
N	31279.000	6.250	564.003	564.013
☉ Brg. Pier 2	31289.000	6.250	564.003	564.003
O	31299.000	6.250	564.003	564.013
P	31309.000	6.250	564.003	564.023
Q	31319.000	6.250	564.003	564.032
R	31329.000	6.250	564.003	564.040
S	31339.000	6.250	564.003	564.040
T	31349.000	6.250	564.003	564.032
U	31359.000	6.250	564.003	564.023
V	31369.000	6.250	564.003	564.013
☉ Brg. Pier 3	31379.000	6.250	564.003	564.003
W	31389.000	6.250	564.003	564.013
X	31399.000	6.250	564.003	564.024
Y	31409.000	6.250	564.003	564.034
Z	31419.000	6.250	564.003	564.042
AA	31429.000	6.250	564.003	564.042
BB	31439.000	6.250	564.003	564.034
CC	31449.000	6.250	564.003	564.025
DD	31459.000	6.250	564.003	564.014
☉ Brg. Pier 4	31469.000	6.250	564.003	564.003
EE	31479.000	6.250	564.003	564.011
FF	31489.000	6.250	564.003	564.020
GG	31499.000	6.250	564.003	564.030
HH	31509.000	6.250	564.003	564.035
II	31519.000	6.250	564.003	564.032
JJ	31529.000	6.250	564.003	564.021
☉ Brg. E. Abut.	31541.000	6.250	564.003	564.003
Bk. E. Abut.	31543.875	6.250	564.003	564.003

DESIGNED	A.R.K.
CHECKED	S.F.M., F.J.S.
DRAWN	S.A.P.
CHECKED	A.R.K., F.J.S.

TOP OF SLAB ELEVATIONS

SECTION 94-00087-00-BR
COUNTY HIGHWAY 23 - FAS ROUTE 429
HANCOCK COUNTY
STA. 313+34

4440 ASH GROVE SPRINGFIELD, IL 62711 (217) 793-8600 ossinc@famvid.com	OZYURT AND STONE, INC. CONSULTING ENGINEERS	JOB NO.: 0319 FILE: 0319SLABEL3.DGN DATE: 08/24/05
--	---	--