

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
*	**	SALINE	119	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

•SAHARA WOODS SFWA CONTRACT NO. 98834  
 \*\*INTERNAL PARK ROADS - SFWA

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				FO00	YO30-1E
				100% STATE	100% STATE
20100500	TREE REMOVAL, ACRES	ACRE	1.30	1.30	
20200100	EARTH EXCAVATION	CU YD	3818	3818	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1489	1489	
20400100	BORROW EXCAVATION	CU YD	8905	8905	
20900310	POROUS GRANULAR BACKFILL	TON	248	248	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	840	840	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	840	840	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	840	840	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	14	14	
25001700	SEEDING, CLASS 3 (MODIFIED)	ACRE	7.0	7.0	
25100115	MULCH, METHOD 2	ACRE	7.0	7.0	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2100.0	2100.0	
28000300	TEMPORARY DITCH CHECKS	EACH	70	70	
28000400	PERIMETER EROSION BARRIER	FOOT	4058	4058	
28000500	INLET AND PIPE PROTECTION	EACH	14	14	
28100207	STONE RIPRAP, CLASS A4	TON	356	356	
28200200	FILTER FABRIC	SQ YD	534	534	
35100100	AGGREGATE BASE COURSE, TYPE A	TON	24,890	24,890	
35800100	PREPARATION OF BASE	SQ YD	33,781	33,781	
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	46,244	46,244	
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	GALLON	126,738	126,738	1
40300500	COVER COAT AGGREGATE	TON	2,129	2,129	
40300600	SEAL COAT AGGREGATE	TON	1,064	1,064	
50100100	REMOVAL OF EXISTING STRUCTURE	EACH	1	1	
50105220	PIPE CULVERT REMOVAL	FOOT	356	356	
542D0217	PIPE CULVERTS, CLASS D, TYPE 1, 12"	FOOT	118	118	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1, 15"	FOOT	182	182	
542D0223	PIPE CULVERTS, CLASS D, TYPE 1, 18"	FOOT	84	84	
542D0229	PIPE CULVERTS, CLASS D, TYPE 1, 24"	FOOT	169	169	
542D0241	PIPE CULVERTS, CLASS D, TYPE 1, 36"	FOOT	72	72	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9	
67100100	MOBILIZATION	L SUM	1	1	

△ Rev. 1-9-06