

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SALINE	119	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*SAHARA WOODS SFWA CONTRACT NO. 98834
 **INTERNAL PARK ROADS - SFWA

TREE REMOVAL SCHEDULE

LOCATION	AREA	STATION	OFFSET	STATION	OFFSET	STATION	OFFSET	STATION	OFFSET
	ACRES		FEET		FEET		FEET		FEET
BOAT LOT									
AREA 1	0.75	4+08	0	4+80	-5	5+28	-20	5+62	-37
		6+58	46	7+10	34	7+59	11	8+77	-16
		9+06	-12	9+41	-15	9+15	-17	9+05	-23
		8+97	-23	5+93	-68	5+00	-99	4+70	-97
		4+61	-88	4+53	-75	4+41	-55	4+35	-26
		4+27	-18	4+08	-18				
SHAY RD.									
AREA 1	0.03	502+78	-24	503+08	-26	503+08	-18	503+61	-19
AREA 2	0.04	506+32	-19	507+91	-26	508+41	-17	509+58	-18
AREA 3	0.03	512+00	-15	512+32	-15	512+32	-17	512+64	-17
AREA 4	0.02	514+92	-15	515+00	-19	516+01	-20	516+01	-11
AREA 5	0.04	515+73	17	516+86	12	516+18	9	517+00	24
		517+91	15						
AREA 6	0.18	516+01	-20	516+70	-11	516+41	-18	517+01	-15
		517+50	-11	517+50	-15	518+01	-15	519+00	-9
		519+00	-35	520+00	-17	521+00	-12	521+00	-17
		521+61	-17	521+80	-11	521+80	-17	522+01	-16
		523+00	-13	523+00	-37	523+97	-20	523+79	-12
AREA 7	0.01	518+24	15	518+98	15	518+98	18	519+77	16
AREA 8	0.01	522+35	27	522+85	18	522+98	28	523+19	26
AREA 9	0.01	526+51	23	526+66	17	526+66	22	526+85	19
AREA 10	0.01	528+02	-20	528+29	-10	528+29	-20	528+65	-21
AREA 11	0.01	532+15	-14	532+50	-12	532+50	-16	532+80	-14
AREA 12	0.01	533+13	-13	533+75	-4	533+78	-4	534+00	-10
AREA 13	0.03	533+50	11	533+79	3	534+00	9	534+00	3
		534+15	5	534+53	14				
AREA 14	0.10	535+32	-17	535+47	-7	536+08	-7	536+24	-14
		536+46	-19	536+53	-18	536+73	-11	537+00	-11
		538+14	-10	539+85	-27	540+12	-22	540+40	-24
		540+00	-32	538+00	-14	537+00	-31	536+00	-20
AREA 15	0.02	535+26	12	535+66	11	535+85	17	535+90	11
		536+55	26	536+55	20	536+87	22	536+97	32
TOTAL	1.3								

DRAINAGE STRUCTURE SCHEDULE

LOCATION STATION	EXISTING STRUCTURE	PIPE CULVERTS CLASS D, TYPE 1					PIPE CULVERT REMOVAL FOOT	POROUS GRANULAR BACKFILL TON	STONE RIPRAP CLASS A4 TON	FILTER FABRIC FOR USE WITH RIP RAP SQ. YD.
		12" FT.	15" FT.	18" FT.	24" FT.	36" FT.				
TIPPLE RD.										
106+73	8" STEEL PIPE				32		40	7		
107+03 LT			56					29		
ENTRANCE 3	8" STEEL PIPE						45			
LAKE RD.										
7+22	24" POLY PIPE				42		30	23		
76+00	18" STEEL PIPE					36	40	10		
76+00						36		10		
SHAY RD.										
500+36	15" STEEL PIPE			42			85	5		
500+36				42				4		
511+13 RT	12" STEEL PIPE		36				30	4		
514+31 LT			50							
533+50	8" STEEL PIPE				28		26	11		
537+00					21			3		
554+00					24			6		
558+00					22			5		
* 571+65	12" STEEL PIPE						60			
SHOOTING RANGE RD.										
600+03.9			40					10		
SPUR RD.									356	
201+50		84							534	
BOAT LOT										
9+00		34						2		
TOTALS		118	182	84	169	72	356	129	356	
									534	

* SEE EARTHWORK SCHEDULE FOR BACKFILL MATERIAL AND QUANTITIES