

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SALINE	119	9
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*SAHARA WOODS SFWA CONTRACT NO. 98834
 **INTERNAL PARK ROADS - SFWA

SURFACING SCHEDULE

LOCATION STATION TO STATION	PREPARATION OF BASE	BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS MATERIALS (COVER AND SEAL COAT)	COVER COAT AGGREGATE	SEAL COAT AGGREGATE	AGGREGATE BASE COURSE, TYPE A
	SOYD	GALLON	GALLON	TON	TON	TON
TIPPLE ROAD 100+00 TO 123+00	5496	3004	8244	138	69	2700
HAULAGE ROAD 300+00 TO 374+78.82 374+78.82 TO 384+06.97	18247.54 2270.4	9955 1238	27372 3406	458 57	229 28	
LAKE RD. 400+00 TO 442+54.54 0+00 TO 16+82.12 16+82.12 TO 76+03.08	14605.15	5725 2238 5263	15759 6153 13818	264 104 232	132 52 116	1897 4398
SHAY RD. 500+24 TO 531+00 531+00 TO 571+76.39	7620.2	4152 3624	11433 9513	192 160	96 80	3538 3028
SPUR RD. 374+78.2 TO 384+07.0	3035	1615	4554	76	38	1421
SHOOTING RANGE ROAD 600+00 TO 627+71		3695	10161	170	85	3100
BOAT LOT	3639	1911	5460	92	46	1732
HEADQUARTERS LOT	1978	1043	2967	50	25	
CAR LOT 1		244	666	12	6	242
CAR LOT 2		279	753	14	7	270
CAR LOT 3		257	693	12	6	252
CAR LOT 4		1506	4428	74	37	1428
TOTALS	56891	45749	125380	2105	1052	24006

SEEDING SCHEDULE

LOCATION STATION TO STATION	SEEDING, CLASS 3 (MODIFIED)	NITROGEN FERTILIZER NUTRIENT	PHOSPHOROUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2
	ACRE	POUND	POUND	POUND	TON	ACRE
TIPPLE ROAD RT. STA. 100+00 TO STA. 124+42.9	0.5	60	60	60	1.0	0.5
TIPPLE ROAD LT. STA. 100+00 TO STA. 124+42.9	1.0	120	120	120	2.0	1.0
LAKE ROAD RT. STA. 0+00 TO STA. 76+03.08	0.7	84	84	84	1.4	0.7
LAKE ROAD LT. STA. 0+00 TO STA. 76+03.08	0.7	84	84	84	1.4	0.7
SHAY ROAD RT. STA. 500+13.26 TO STA. 571+76.39	1.5	180	180	180	3.0	1.5
SHAY ROAD LT. STA. 500+13.26 TO STA. 571+76.39	1.4	168	168	168	2.8	1.4
SPUR RD. STA. 200+00 TO STA. 204+42.23	1.0	120	120	120	2.0	1.0
BOAT LOT STA. 4+21.14 TO STA. 10+00	0.2	24	24	24	0.4	0.2
TOTAL	7.0	840	840	840	14.0	7.0