

F.A.P. R/E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SALINE	119	11
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*SAHARA WOODS SFWA CONTRACT NO. 98834
 **INTERNAL PARK ROADS - SFWA

TEMPORARY DITCH CHECK SCHEDULE

LOCATION STATION	TEMPORARY DITCH CHECKS EACH
TIPPLE RD.	
105+55 LT	1
106+20 LT	1
111+80 LT	1
115+00 LT	1
116+15 LT	1
117+85 LT	1
119+00 LT	1
SHAY RD.	
501+00 RT	1
501+30 LT	1
501+80 RT	1
502+00 LT	1
502+60 RT	1
503+50 RT	1
504+30 RT	1
509+60 LT	1
511+50 LT	1
511+50 RT	1
512+75 LT	1
513+00 RT	1
514+00 RT	1
514+70 LT	1
515+20 LT	1
515+80 RT	1
516+10 LT	1
516+90 LT	1
521+80 RT	1
523+50 RT	1
525+00 RT	1
525+60 LT	1
526+60 LT	1
527+60 LT	1
528+30 LT	1
529+40 LT	1
530+50 LT	1
535+00 LT	1
535+55 LT	1
536+00 LT	1
536+20 RT	1
536+70 LT	1
536+90 RT	1
537+50 LT	1
538+90 LT	1
539+80 LT	1
541+30 LT	1
541+50 RT	1
542+50 RT	1
542+80 LT	1
543+55 RT	1
544+45 RT	1
544+65 LT	1
546+30 RT	1
547+60 RT	1
549+25 RT	1
550+95 RT	1
552+80 RT	1
554+60 RT	1
555+80 RT	1
556+90 RT	1
557+60 RT	1
558+70 LT	1
559+30 RT	1
559+80 LT	1
562+30 LT	1
562+50 RT	1
563+45 LT	1
563+60 RT	1
564+20 RT	1
564+25 LT	1
564+80 RT	1
565+60 LT	1
TOTAL	70

PERIMETER EROSION BARRIER SCHEDULE

LOCATION STATION TO STATION	PERIMETER EROSION BARRIER FOOT
TIPPLE RD.	
102+00 RT TO 104+00 RT	200
103+00 LT TO 104+50 LT	150
SHAY RD.	
501+00 RT TO 503+00 RT	200
508+00 RT TO 510+00 RT	200
515+00 RT TO 520+00 RT	500
519+00 LT TO 525+00 LT	600
538+00 RT TO 541+00 RT	300
567+00 LT TO 572+00 LT	500
566+00 RT TO 572+00 RT	600
SPUR RD.	
200+00 LT TO 201+00 LT	100
200+00 RT TO 201+00 RT	100
BOAT LOT	
4+21 LT TO 9+00 LT	479
4+21 RT TO 5+50 RT	129
TOTAL	4058

INLET AND PIPE PROTECTION SCHEDULE

LOCATION STATION	OFFSET FEET	INLET AND PIPE PROTECTION EACH
TIPPLE RD.		
106+73	16' LT	1
107+35 LT	20' LT	1
LAKE RD.		
7+22	20' RT	1
76+00	20' RT	1
SHAY RD.		
500+36	21' LT	1
511+05	20' RT	1
514+31	20' LT	1
533+50	15' LT	1
537+00	14' LT	1
554+00	15' RT	1
558+00	14' RT	1
SPUR RD.		
201+50	25' RT	1
BOAT LOT		
9+00	17' RT	1
SHOOTING RANGE ROAD		
600+12	18.5' LT	1
TOTAL		14

SIGN SCHEDULE

LOCATION STATION	SIGN DESCRIPTION	SIGN CODE	SIGN PANEL DIMENSIONS	SIGN PANEL TYPE 1	WOOD SIGN SUP.
			W x H (FT)	SQ FT	FT
LAKE RD.					
415+00	SPEED LIMIT 25	R2-1	1.5 x 2	3.0	13.0
14+75	SPEED LIMIT 25	R2-1	1.5 x 2	3.0	14.0
16+57	ONE WAY		1.5 x 2	3.0	13.0
25+00	SPEED LIMIT 25	R2-1	1.5 x 2	3.0	13.0
52+00	DO NOT ENTER	R5-1	2.5 x 2.5	6.3	15.0
52+55	ONE WAY	R6-IR	3 x 1	3.0	13.5
73+33	DO NOT ENTER	R5-1	2.5 x 2.5	6.3	12.5
73+83	ONE WAY	R6-IL	3 x 1	3.0	11.0
SHAY RD.					
530+60	ONE WAY	R6-IR	3 x 1	3.0	13.0
530+75	DO NOT ENTER	R5-1	2.5 x 2.5	6.3	13.5
547+08	CAUTION CURVE	W1-2	2 x 2	4.0	13.0
547+08	15 M.P.H.	W13-1	1.5 x 1.5	2.3	
566+09	CAUTION CURVE	W1-2	2 x 2	4.0	13.0
566+09	15 M.P.H.	W13-1	1.5 x 1.5	2.3	
570+00	SPEED LIMIT 15	R2-1	1.5 x 2	3.0	12.5
SPUR RD.					
200+19	STOP	R1-1	2.5 x 2.5	6.3	12.5
TOTALS				61.6	182.5