

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
B65	SMART FY 05-08	PERRY	11	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES				STP-RURAL-STATE 80% FED / 20% STATE PERRY COUNTY	STP-URBAN-STATE 80% FED / 20% STATE PERRY COUNTY	STP-URBAN-STATE 80% FED / 20% STATE PERRY COUNTY
CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	1000 QUANTITY	1000 QUANTITY	1025 QUANTITY
X0322729	MATERIAL TRANSFER DEVICE	TON	6136.9	5448.8	434.6	253.5
X4066428	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX D, N90	TON	6136.9	5448.8	434.6	253.5
35102000	AGGREGATE BASE COURSE TYPE B, 8"	SO YD	494.2	494.2		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6540.5	5803.3	465.6	271.6
40600300	AGGREGATE (PRIME COAT)	TON	109.3	97.0	7.8	4.5
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10.8	9.3	1.4	
40600895	CONSTRUCTING TEST STRIP	EACH	1.0	0.9	0.1	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SO YD	427.0	427.0		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	122.2	122.2		
40600990	TEMPORARY RAMP	SO YD	141.0	106.4	26.6	8.0
40800040	INCIDENTAL BITUMINOUS SURFACE	TON	124.9	124.2	0.7	
44000002	BITUMINOUS SURFACE REMOVAL 1/2"	SO YD	64268.0	64268.0		
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SO YD	8192.0		5174.0	3018.0
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SO YD	1148.7	980.9	167.8	
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	817.1	773.4	43.7	
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	81.2	81.2	0.0	
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	111.1	106.2	4.9	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	43393.0	43393.0		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1273.6	1273.6		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3.0	1.8	1.2	
67100100	MOBILIZATION	L SUM	1.0	0.7	0.3	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	1.0		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	1.0		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1.0	1.0		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0		0.5	0.5
70300100	SHORT- TERM PAVEMENT MARKING	FOOT	5577.5	4915.8	661.7	
70300220	TEMPORARY PAVEMENT MARKING, LINE 4"	FOOT	74015.0	73508.0	507.0	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	24671.6	24502.6	169.0	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	74015.0	73508.0	507.0	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	363.0	338.0	25.0	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	363.0	338.0	25.0	

*SPECIALTY ITEMS