

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
865	SMART FY 05-08	PERRY	11	8
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

PAVEMENT MARKING SCHEDULE

STATION	LENGTH	4" YELLOW SKIP DASH	4" YELLOW SKIP DASH & NO PASSING	4" DOUBLE SOLID YELLOW	4" WHITE EDGE LINES	RAISED REFLECTIVE PAVEMENT MARKERS	RAISED REFLECTIVE PAVEMENT MARKING REMOVAL	SHORT TERM PAVEMENT MARKING (2 APPL.)	TEMP. PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL
		(FT)	(FT)	(FT)	(FT)	(FT)	(EACH)	(EACH)	(FT)	(FT)
950+22 TO 949+02	120.0		150.0		240.0	1.5	1.5	21.8	390.0	130.0
949+02 TO 872+82	7620.0	1905.0			15240.0	95.3	95.3	1385.5	17145.0	5715.0
872+82 TO 867+50	531.6	132.9			1063.2	6.6	6.6	96.7	1196.1	398.7
867+50 BK = 0+00 AH										
0+00 TO 3+57	357.4		446.7			4.5	4.5	65.0	1161.5	387.2
3+57 TO 4+72	115.0			230.0		1.4	1.4	20.9	460.0	153.3
4+72 TO 13+92	920.0		1150.0		1840.0	11.5	11.5	167.3	2990.0	996.7
13+92 TO 14+24	32.0	8.0			64.0	0.4	0.4	5.8	72.0	24.0
14+24 TO 20+77	653.0		816.3		1306.0	8.2	8.2	118.7	2122.3	707.4
20+77 TO 24+73	396.0	99.0			792.0	5.0	5.0	72.0	891.0	297.0
24+73 TO 30+97	624.0		780.0		1248.0	7.8	7.8	113.5	2028.0	676.0
30+97 TO 42+74	1177.0	294.3			2354.0	14.7	14.7	214.0	2648.3	882.8
42+74 TO 50+78	804.0		1005.0		1608.0	10.1	10.1	146.2	2613.0	871.0
50+78 TO 53+09	231.0			462.0	462.0	2.9	2.9	42.0	924.0	308.0
53+09 TO 61+53	844.0		1055.0		1688.0	10.6	10.6	153.5	2743.0	914.3
61+53 TO 73+68	1215.0	303.8			2430.0	15.2	15.2	220.9	2733.6	911.3
73+68 TO 80+74	706.0		882.5		1412.0	8.8	8.8	128.4	2294.5	764.8
80+74 TO 84+40	366.0	91.5			732.0	4.6	4.6	66.5	823.5	274.5
84+40 TO 88+77	437.0		546.3		874.0	5.5	5.5	79.5	1420.3	473.4
88+77 TO 90+54	177.0			354.0	354.0	2.2	2.2	32.2	708.0	236.0
90+54 TO 98+46	792.0		990.0		1584.0	9.9	9.9	144.0	2574.0	858.0
98+46 TO 99+71	125.0	31.3			250.0	1.6	1.6	22.7	281.3	93.8
99+71 TO 108+35	864.0		1080.0		1728.0	10.8	10.8	157.1	2808.0	936.0
108+35 TO 111+51	316.0	79.0			632.0	4.0	4.0	57.5	711.0	237.0
111+51 TO 119+88	837.0		1046.3		1674.0	10.5	10.5	152.2	2720.3	906.8
119+88 TO 122+78	290.0	72.5			580.0	3.6	3.6	52.7	652.5	217.5
122+78 TO 130+32	754.0		942.5		1506.0	9.4	9.4	137.1	2450.5	816.8
130+32 TO 162+08	3176.0	794.0			6352.0	39.7	39.7	577.5	7146.0	2382.0
162+08 TO 174+04	1196.0		1495.0		2392.0	15.0	15.0	217.5	3887.0	1295.7
174+04 TO 180+57	653.0			1306.0	1306.0	8.2	8.2	118.7	2612.0	870.7
180+57 TO 187+65	708.0		885.0		1416.0	8.9	8.9	128.7	2301.0	767.0
PAVING OMISSION: STATION 187+65.0 TO STATION 249+15.0										
SUBTOTAL - RURAL SECTION		73507.7								
249+15 TO 249+26	11.0	2.6			22.0	338.0	338.0	4915.8	73507.7	24502.6
249+26 TO 268+55	1929.0	482.3				0.1	0.1	2.0	24.8	8.3
SUBTOTAL - URBAN SECTION		507.0								
TOTALS		74014.7								
						362.2	362.2	5577.5	74014.7	24671.6