



- NOTES**
- See Sheets 58 and 59 for Details and Bill of Material.
 - Reinforcement bars designated (E) shall be epoxy coated. See Special Provisions.
 - Bars indicated thus: 20x3 #5 etc. indicates 20 lines of bars with 3 lengths per line.
 - Minimum lap for #5 bars is 2'-2".
 - For Sections A-A, B-B and D-D, See Sheet 58.
 - W12x14 Support Beams and Expansion Joint Support Angles are paid for by the Unit Bid Price per pound for "Furnishing and Erecting Structural Steel." See Table of Bill of Material, Sheet 59.
 - Shall see Span

DESIGNED	<i>[Signature]</i>
CHECKED	R.E.C.
DRAWN	<i>[Signature]</i>
CHECKED	R.E.C. - F.S.

SECTIONS THRU EXISTING DECK

ILLINOIS APPROACH SPANS:
Total Number of Existing Purlins = 462
Total Number of Existing Rail Posts (Both Sides) = 378
Approximate Quantity of Existing Reinforced Concrete Deck = 571 Cu. Yds.

BRIDGE NO. 1
STRUCTURE 002-0005
FOR INFORMATION ONLY

ILLINOIS APPROACH SPANS
DECK PLANS AND SECTIONS
CONCRETE FLOOR ALTERNATE
F.A.U.S. Rte. 9811 (U.S. 60 & 62)
S.B.I. 150 SECTION 138 D-BR
ALEXANDER CO., IL. MISSISSIPPI CO., MO.
STATION 28 + 13.08