

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	80% FED. 20% STATE					CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	80% FED. 20% STATE				
				0005									0005				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	65	65					70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	275	275				
25200110	SODDING, SALT TOLERANT	SO YD	65	65					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1025	1025				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	130	130					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	2200	2200				
40600300	AGGREGATE (PRIME COAT)	TON	650	650					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	5780	5780				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	245	245					*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	2730	2730				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	65450	65450				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1240	1240					*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	12575	12575				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	330	330					*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	275	275				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	15950	15950					*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1025	1025				
42001300	PROTECTIVE COAT	SO YD	385	385					*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	2200	2200				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	1150	1150					*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2495	2495				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	162675	162675					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3380	3380				
44000600	SIDEWALK REMOVAL	SO FT	1150	1150					*88600600	DETECTOR LOOP REPLACEMENT	FOOT	5001	5001				
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SO YD	1475	1475					40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	6835	6835				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	1825	1825					Δ X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	7700	7700				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	245	245					X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	77	77				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	300	300					Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1150	1150				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	5	5					Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	25	25				
60404950	FRAMES AND GRATES, TYPE 24	EACH	5	5					Δ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	220	220				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
67100100	MOBILIZATION	L SUM	1	1					Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1													
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1													
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1													
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1													
70300100	SHORT TERM PAVEMENT MARKING	FOOT	52025	52025													
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	2730	2730													
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	65450	65450													
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	12575	12575													

* SPECIALTY ITEMS
Δ NON-PARTICIPATING (100% STATE)