

# SUMMARY OF QUANTITIES

801.FED./201.STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				0004 ROADWAY	0011 STRUCTURE	0021 TRAFFIC SIGNALS
X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	1	0	0	1
20101100	TREE TRUNK PROTECTION	EACH	1	1	0	0
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	1	1	0	0
20101700	SUPPLEMENTAL WATERING	UNIT	1.5	1.5	0.0	0.0
20200100	EARTH EXCAVATION	CU YD	74	74	0	0
20400800	FURNISHED EXCAVATION	CU YD	74	74	0	0
20800150	TRENCH BACKFILL	CU YD	15	15	0	0
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	684	684	0	0
25100630	EROSION CONTROL BLANKET	SQ YD	684	684	0	0
25200110	SODDING, SALT TOLERANT	SQ YD	684	684	0	0
28000510	INLET FILTERS	EACH	21	21	0	0
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	273	273	0	0
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	665	665	0	0
40600300	AGGREGATE (PRIME COAT)	TON	14	14	0	0
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	1	1	0	0
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	139	139	0	0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	130	130	0	0
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	279	279	0	0
42001100	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	86	86	0	0
42001300	PROTECTIVE COAT	SQ YD	216	216	0	0
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	94	94	0	0
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	33	33	0	0
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	434	434	0	0
42400800	DETECTABLE WARNINGS	SQ FT	40	40	0	0
44000100	PAVEMENT REMOVAL	SQ YD	810	810	0	0
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	3,159	3,159	0	0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	823	823	0	0
44000600	SIDEWALK REMOVAL	SQ FT	311	311	0	0
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1,392	1,392	0	0
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	0	1	0
50102400	CONCRETE REMOVAL	CU YD	66.4	0.0	66.4	0.0
50200100	STRUCTURE EXCAVATION	CU YD	82	0	82	0
50300225	CONCRETE STRUCTURES	CU YD	102.8	0.0	102.8	0.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	404.0	0.0	404.0	0.0
50300260	BRIDGE DECK GROOVING	SQ YD	826	0	826	0

801.FED./201.STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				0004 ROADWAY	0011 STRUCTURE	0021 TRAFFIC SIGNALS
50300300	PROTECTIVE COAT	SQ YD	1,082	0	1,082	0
50500305	ERECTING STRUCTURAL STEEL	L SUM	1.0	0.0	1.0	0.0
50500505	STUD SHEAR CONNECTORS	EACH	3,636	0	3,636	0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	94,620	0	94,620	0
50800515	BAR SPLICERS	EACH	623	0	623	0
51500100	NAME PLATES	EACH	1	0	1	0
52000110	PREFORMED JOINT STRIP SEAL	FOOT	145	0	145	0
52100210	ERECTING ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12	0	12	0
52100505	ANCHOR BOLTS, 5/8"	EACH	24	0	24	0
52100520	ANCHOR BOLTS, 1"	EACH	24	0	24	0
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	40	40	0	0
58700300	CONCRETE SEALER	SQ FT	1,159	0	1,159	0
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	75	0	75	0
60207115	CATCH BASINS, TYPE C, TYPE 3V FRAME AND GRATE	EACH	4	4	0	0
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	3	3	0	0
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	756	756	0	0
60618210	HOT-MIX ASPHALT MEDIAN SURFACE, 4 INCH	SQ FT	259	259	0	0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9	0	0
67100100	MOBILIZATION	L SUM	1.0	1.0	0.0	0.0
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1.0	1.0	0.0	0.0
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1.0	1.0	0.0	0.0
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1.0	1.0	0.0	0.0
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	32	32	0	0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5,318	5,318	0	0
70400100	TEMPORARY CONCRETE BARRIER	FOOT	460	460	0	0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	290	290	0	0
72000200	SIGN PANEL - TYPE 2	SQ FT	28	28	0	0
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	6	6	0	0
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9,174	9,174	0	0
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	54	54	0	0
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	149	149	0	0
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	686	686	0	0
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	32	32	0	0
78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	8	8	0	0
78300100	PAVEMENT MARKING REMOVAL	SQ FT	3,640	3,640	0	0



\* SPECIALTY ITEMS

FILE NAME = G:\projects\2102155\_004\CADD\Civil\Sheet\002\1688E2-82.rvt-500.dgn



USER NAME = 2bookd	DESIGNED - DLP	REVISED -
PLOT SCALE = 50.0000' / IN.	DRAWN - ENTRAN	REVISED -
PLOT DATE = 12/12/2011	CHECKED - TMH	REVISED -
	DATE - 10/28/11	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>WOLF ROAD OVER PALATINE ROAD SUMMARY OF QUANTITIES</b>			
SCALE: 50.0000' / IN.	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.U. RTE. 2692	SECTION 1415B-1	COUNTY COOK	TOTAL SHEETS 72	SHEET NO. 3
CONTRACT NO. 60M52				
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT				