

SUMMARY OF QUANTITIES

80% FED./20% STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				0004 ROADWAY	0011 STRUCTURE	0021 TRAFFIC SIGNALS
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	32	32	0	0
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	40	0	0	40
81101000	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., GALVANIZED STEEL	FOOT	190	0	0	190
81400300	DOUBLE HANDHOLE	EACH	2	0	0	2
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1	0	0	1
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,953	0	0	1,953
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2,582	0	0	2,582
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2,016	0	0	2,016
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1,568	0	0	1,568
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	627	0	0	627
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	6	0	0	6
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2	0	0	2
88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	4	0	0	4
88055160	OPTICALLY PROGRAMMED SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	2	0	0	2
88055170	OPTICALLY PROGRAMMED SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	4	0	0	4
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	16	0	0	16
88500100	INDUCTIVE LOOP DETECTOR	EACH	8	0	0	8
88600100	DETECTOR LOOP, TYPE I	FOOT	769	0	0	769
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1	0	0	1
89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	1	0	0	1
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	7,728	0	0	7,728
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	0	0	1
89502376	REBUILD EXISTING HANDHOLE	EACH	1	0	0	1
89502380	REMOVE EXISTING HANDHOLE	EACH	2	0	0	2
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	72	0	72	0
X4403800	MEDIAN SURFACE REMOVAL	SQ FT	259	259	0	0
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	23	23	0	0
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1.0	1.0	0.0	0.0
X7030025	WET REFLECTIVE TEMPORARY TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	91	91	0	0
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	14,537	14,537	0	0
X7030055	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	FOOT	190	190	0	0
X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	1,143	0	0	1,143
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	28	0	28	0
Z0004552	APPROACH SLAB REMOVAL	SQ YD	319	319	0	0
Z0007122	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	135	0	135	0

* SPECIALTY ITEMS

80% FED./20% STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				0004 ROADWAY	0011 STRUCTURE	0021 TRAFFIC SIGNALS
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.0	1.0	0.0	0.0
Z0018004	DRAINAGE SCUPPERS, DS-12	EACH	2	0	2	0
Z0018800	DRAINAGE SYSTEM	L SUM	1.0	0.0	1.0	0.0
Z0026407	TEMPORARY SHEET PILING	SQ FT	212	0	212	0
Z0030275	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 2	EACH	3	3	0	0
Z0030355	IMPACT ATTENUATORS, RELOCATE (SEVERE USE), TEST LEVEL 2	EACH	3	3	0	0
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	147	147	0	0
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	146	0	146	0
Z0062456	TEMPORARY PAVEMENT	SQ YD	496	496	0	0
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1	0	0	1

* SPECIALTY ITEMS

FILE NAME: C:\projects\2102155_8099\CAD\Civil\Sheet\02\SUMMARY OF QUANTITIES.dwg



USER NAME = 2bookd	DESIGNED - DLP	REVISED -
PLOT SCALE = 50.0000' / IN.	DRAWN - ENTRAN	REVISED -
PLOT DATE = 12/12/2011	CHECKED - TMH	REVISED -
	DATE - 10/28/11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

WOLF ROAD OVER PALATINE ROAD SUMMARY OF QUANTITIES			
F.A.U. RTE. 2692	SECTION 1415B-1	COUNTY COOK	TOTAL SHEETS 72
SCALE: 50.0000' / IN.		SHEET NO. OF	SHEETS STA. TO STA.

FED. ROAD DIST. NO. 1	ILLINOIS FED. AID PROJECT	CONTRACT NO. 60M52
-----------------------	---------------------------	--------------------