

SCHEDULE OF QUANTITIES

952+23.6	13.1 RT	-	956+53.0	2.9 LT	429.7
956+53.0	2.9 LT	-	956+96.6	2.9 LT	43.6
957+57.8	2.8 LT	-	964+63.7	1.8 LT	705.9

SOUTH FRONTAGE RD. CL
WHITE LINE

101+26.6	10.7 RT	-	104+67.4	23.7 RT	341.0
104+67.4	23.7 RT	-	105+31.3	26.7 RT	64.0
105+31.3	26.7 RT	-	106+02.8	101.1 RT	113.7
100+00.0	11.3 LT	-	101+52.6	0.1 LT	153.0
101+52.6	0.1 LT	-	101+90.9	0.4 LT	38.3
101+90.9	0.4 LT	-	104+68.1	8.7 RT	277.3
104+68.1	8.7 RT	-	105+67.4	15.7 RT	99.6
106+74.4	19.1 RT	-	107+29.2	13.3 RT	55.1

PALATINE RD. CL- NORTH FRONTAGE RD.
WHITE LINE

1340+77.8	83.5 LT	-	1342+30.3	84.8 LT	152.5
1342+30.3	84.8 LT	-	1342+79.8	135.1 LT	78.5
1343+29.0	72.8 LT	-	1343+95.7	72.2 LT	66.7
1343+95.7	72.2 LT	-	1347+24.5	58.5 LT	329.1

TOTAL = 14,537

X7030055 WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH

STATION	OFFSET(FT)	-	STATION	OFFSET(FT)	FOOT
---------	------------	---	---------	------------	------

STAGE 1
WOLF RD. CL

948+98.7	14.5 LT	-	948+98.7	2.0 RT	16.5
951+24.2	10.7 LT	-	951+24.2	38.2 LT	27.4

SOUTH FRONTAGE RD. CL

105+56.4	40.4 RT	-	105+66.1	19.6 RT	22.9
105+66.1	19.6 RT	-	105+65.9	5.8 RT	13.8

PALATINE RD. CL- NORTH FRONTAGE RD.

1343+30.4	71.9 LT	-	1343+30.3	87.0 LT	15.2
-----------	---------	---	-----------	---------	------

STAGE 2
WOLF RD. CL

948+98.7	14.8 RT	-	948+98.7	42.7 RT	27.9
951+23.2	13.0 RT	-	951+23.2	0.6 RT	12.4

SOUTH FRONTAGE RD. CL

105+66.2	37.2 RT	-	105+66.1	15.6 RT	21.7
----------	---------	---	----------	---------	------

PALATINE RD. CL- NORTH FRONTAGE RD.

1343+30.4	72.8 LT	-	1343+30.1	105.3 LT	32.6
-----------	---------	---	-----------	----------	------

TOTAL = 190

Z0004552 APPRACH SLAB REMOVAL

STATION	WIDTH(FT)	-	STATION	WIDTH(FT)	SQ YD
949+41.4	57.5	-	949+66.4	57.5	159.7
950+33.6	57.3	-	950+58.6	57.3	159.2

TOTAL = 319

Z0030275 IMPACT ATTENUATORS, TEMPORARY (SEVERE USE,NARROW),
TEST LEVEL 2

STATION	OFFSET(FT)	EACH
PALATINE RD. CL- STAGE 1		
1344+01.9	64.6 LT	1.0
WOLF RD.		
950+72.0	4.0 LT	1.0
949+26.0	4.0 LT	1.0

TOTAL = 3

Z0030355 IMPACT ATTENUATORS, RELOCATE (SEVERE USE),
TEST LEVEL 2

STATION	OFFSET(FT)	EACH
S. FRONTAGE RD - STAGE 2		
104+00.0	4.5 LT	1.0
WOLF RD		
949+26.0	4.0 RT	1.0
950+72.0	4.0 RT	1.0

TOTAL = 3

Z0030850 TEMPORARY INFORMATION SIGNING

STATION	WIDTH(FT)	-	STATION	WIDTH(FT)	SQ FT
ROAD WORK SIGN - WOLF RD. N END					
ROAD WORK SIGN - WOLF RD. S END					
ROAD WORK SIGN - SOUTH FRONTAGE RD. W END					
ROAD WORK SIGN - NORTH FRONTAGE RD. E END					
DRIVEWAY ENTRANCE SIGN					
DRIVEWAY ENTRANCE SIGN					
DRIVEWAY ENTRANCE SIGN					
DRIVEWAY ENTRANCE SIGN					
DRIVEWAY ENTRANCE SIGN					
DRIVEWAY ENTRANCE SIGN					

TOTAL = 147

Z0062456 TEMPORARY PAVEMENT

STATION	WIDTH(FT)	-	STATION	WIDTH(FT)	SQ YD
S. FRONTAGE RD CL					
101+20.1	1.2	-	104+89.4	14.8	328.4
104+89.4	14.8	-	104+89.8	13.8	0.6
104+89.8	13.8	-	105+16.8	10.4	36.3
105+16.8	10.4	-	105+28.2	11.4	13.7
105+28.2	11.4	-	105+39.3	12.4	14.8
105+39.3	12.4	-	105+50.5	15.5	17.3
SHIFT TO WOLF RD CL					
949+08.3	0.0	-	948+92.9	12.0	11.4
948+92.9	12.0	-	948+77.9	9.4	17.9
948+77.9	9.4	-	948+57.0	7.3	19.4
948+57.0	9.2	-	947+96.8	1.7	36.5

TOTAL = 496

FILE NAME = G:\prj\sect\2102195_009\LCADD\CADD\1\SHS\002\016\0452-05\skt-schedule.dgn