

SUMMARY OF QUANTITIES

80% FED / 20% STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				ROADWAY 0004	STRUCTURES 0014
20100110	TREE REMOVAL (6 TO 15 INCHES DIAMETER)	UNIT	8	8	0
20200100	EARTH EXCAVATION	CU YD	161	161	0
20400000	FURNISHED EXCAVATION	CU YD	65	65	0
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	765	765	0
25000210	SEEDING, CLASS 2A	ACRE	0.1	0.1	0.0
25000312	SEEDING, CLASS 4A	ACRE	0.1	0.1	0.0
25100630	EROSION CONTROL BLANKET	SO YD	765	765	0
28000305	TEMPORARY DITCH CHECKS	FOOT	15	15	0
28000400	PERIMETER EROSION BARRIER	FOOT	804	804	0
28000510	INLET FILTERS	EACH	1	1	0
28100107	STONE RIPRAP, CLASS A4	SO YD	344	11	333
28200200	FILTER FABRIC	SO YD	344	11	333
31102300	SUBBASE GRANULAR MATERIAL, TYPE C 6"	SO YD	410	410	0
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	19	19	0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	196	196	0
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	33	33	0
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2	2	0
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	67	67	0
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SO YD	60	60	0
44000100	PAVEMENT REMOVAL	SO YD	40	40	0
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	793	793	0
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	26	26	0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	298	298	0
44004250	PAVED SHOULDER REMOVAL	SO YD	239	239	0
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	35	35	0
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	338	338	0
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	0	1
50102400	CONCRETE REMOVAL	CU YD	68	0	68
50200100	STRUCTURE EXCAVATION	CU YD	278	0	278
50300100	FLOOR DRAINS	EACH	6	0	6
50300225	CONCRETE STRUCTURES	CU YD	153.6	0	153.6
50300255	CONCRETE SUPERSTRUCTURE	CU YD	293.6	0	293.6
50300260	BRIDGE DECK GROOVING	SO YD	571	0	571
50300300	PROTECTIVE COAT	SO YD	715	0	715
50500305	ERECTING STRUCTURAL STEEL	L SUM	1.0	0.0	1.0

80% FED / 20% STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				ROADWAY 0004	STRUCTURES 0014
50500505	STUD SHEAR CONNECTORS	EACH	2,880	0	2,880
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	92,280	0	92,280
50800515	BAR SPLICERS	EACH	112	0	112
	FURNISHING ^{SOLDIER} STEEL PILES HP SECTION	FOOT	917	0	917
51203860	TEST PILE STEEL HP14X73	EACH	2	0	2
51204650	PILE SHOES	EACH	31	0	31
51500100	NAME PLATES	EACH	1	0	1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	113	0	113
52100210	ERECTING ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	7	0	7
52100505	ANCHOR BOLTS, 5/8"	EACH	14	0	14
52100520	ANCHOR BOLTS, 1"	EACH	14	0	14
56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1	1	0
58700300	CONCRETE SEALER	SO FT	1,209	0	1,209
59000200	EPOXY CRACK INJECTION	FOOT	5	0	5
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	187	0	187
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	2	2	0
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	3	3	0
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	100	100	0
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	50	50	0
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1	0
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	0
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1	0
63200310	GUARDRAIL REMOVAL	FOOT	601	601	0
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	50	50	0
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1.0	1.0	0.0
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1	0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	0
67100100	MOBILIZATION	L SUM	1.0	1.0	0.0
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1385	1385	0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	6	6	0
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	8	8	0
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	7	7	0
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1	0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	6	6	0
X0325751	DRIVING SOLDIER PILES	FOOT	917	0	917

* SPECIALTY ITEMS

FILE NAME = G:\projects\21021215_000\CADD\Civil\Shrink\B2-0166R78-03.mxd



USER NAME = zpietud
 PLOT SCALE = 50.0000' / 1" IN.
 PLOT DATE = 10/27/2011

DESIGNED - DJB	REVISED -
DRAWN - ENTRAN	REVISED -
CHECKED - TMH	REVISED -
DATE - 10/28/11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**WESTERN AVENUE OVER BUTTERFIELD CREEK
SUMMARY OF QUANTITIES**

SCALE: 0.0000' / 1" IN. SHEET NO. OF SHEETS STA. TO STA.

P&U RTE. 2845	SECTION 0908-B	COUNTY COOK	TOTAL SHEETS	Rev
			52	3
CONTRACT NO. 60M78				