

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES					CONSTRUCTION TYPE CODE: 0005					SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES					CONSTRUCTION TYPE CODE: 0005																
CODE NO	ITEM	UNIT										CODE NO	ITEM	UNIT																							
			0005	0014												0005																					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	106	106								70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1402	1402																					
40600300	AGGREGATE (PRIME COAT)	TON	528	528								* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	36.4	36.4																					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	198	198								* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	131686	131686																					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2								* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	112	112																					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	228	228								* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	56	56																					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	620	620								* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	35	35																					
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	11211	11211								* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	110	110																					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	132148	132148								* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1110	1110																					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	3690	3690								* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	852	852																					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	1322	1322								78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	778	778																					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	950	950								X2020110	GRADING AND SHAPING SHOULDERS	UNIT	889	889																					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	680	680								40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	5451	5451																					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1806	1806								Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	102.8	102.8																					
58700300	CONCRETE SEALER	SO FT	7160																																		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6																																	
67100100	MOBILIZATION	L SUM	1	1																																	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1																																	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1																																	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1																																	
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1																																	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1																																	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	12582	12582																																	
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	36.4	36.4																																	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	131686	131686																																	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	112	112																																	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	56	56																																	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	35	35																																	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	110	110																																	

Rev.