

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIOUS	2011-062-I	WILL & COOK	22	2

**INDEX OF SHEETS**

- 1 TITLE SHEET
- 2 INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES  
*2A GENERAL NOTES*
- 3 SUMMARY OF QUANTITIES
- 4 - 7 LOCATION MAPS
- 8 - 10 BRIDGE PLANS LOCATION 1 (SN 016-0133)
- 11 - 15 BRIDGE PLANS LOCATION 2 (SN 016-0121) & LOCATION 3 (SN 016-0122)
- 16 BRIDGE PLANS LOCATION 4 (SN 016-2405)
- 17 BRIDGE PLANS LOCATION 5 (SN 099-9904)
- 18 BRIDGE PLANS LOCATION 6 (SN 099-0101)
- 19 BRIDGE PLANS LOCATION 7 (SN 099-0239)
- 20 BRIDGE PLANS LOCATION 8 (SN 099-0166)
- 21 BRIDGE PLANS LOCATION 9 (SN 099-9903)
- 22 ARTERIAL ROAD INFORMATION SIGN (TC-22)

**STATE STANDARDS**

- 701301-04 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
- 701501-06 URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
- 701601-07 URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
- 701606-08 URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
- 701901-02 TRAFFIC CONTROL DEVICES

CONTRACTOR TO COORDINATE WITH ILLINOIS DEPARTMENT OF TRANSPORTATION BUREAU OF LAND ACQUISITION, PROPERTY MANAGEMENT SECTION, MIKE CULLIAN AT (847) 705-4280 AT LEAST 14 DAYS PRIOR TO BEGINNING WORK.

**GENERAL NOTES**

CONTRACT NO: 60P81

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION) AT 800-892-0123 OR 811 OR "CUAN" (CHICAGO UTILITY ALERT NETWORK) AT 312-744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE & GAS FACILITIES. (48 HOURS NOTIFICATION REQUIRED)

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, THE CITIES OF CHICAGO AND JOLIET, AND THE VILLAGE OF WORTH.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE OR TOLLWAY PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 FOR ARTERIALS A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

IT SHALL BE THE CONTRACTORS' RESPONSIBILITY TO VERIFY ALL DIMENSIONS & CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION & ORDERING OF MATERIAL.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.

CONTRACTOR SHALL REMOVE OR FIRMLY ATTACH ANY TRAFFIC CONTROL DEVICES TO THE BASCULE BRIDGE DECK THROUGHOUT THE DURATION OF THE IMPROVEMENT, SO THEY WILL NOT FALL OFF THE DECK WHEN THE BRIDGE SPANS ARE RAISED.

THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM THE BUREAU OF MAINTENANCE, BRIDGE INSPECTORS.

CONTRACTOR SHALL PROVIDE SAFE TEMPORARY ACCESS TO THE TENDER HOUSES THROUGHOUT CONSTRUCTION PERIOD.

ILLINOIS DEPARTMENT OF  
TRANSPORTATION

INDEX OF SHEETS  
STATE STANDARDS  
GENERAL NOTES