

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	129-R-2	KANE	243	7
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 62195				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE											
			URBAN	0003 ROADWAY IL. RTE. 64	0021 LIGHTING IL. RTE. 64	0021 T.S. AT 7TH AVE. 80% FED. 10% STATE 10% ST. CH	0021 T.S. AT TYLER 80% FED. 10% STATE 10% ST. CH	0021 T.S. AT DUNHAM 80% FED. 10% STATE 5% ST. CH 5% KANE	0021 INTER CONNECT 80% FED. 20% STATE #	0021 SIGNING	0043 WATER MAIN	0021		
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	80% FED. 20% STATE	100% ST. CHARLES					80% FED. 20% STATE	100% ST. CHARLES	100% ST. CHARLES		
50300225	CONCRETE STRUCTURES	CU YD	140.5	140.5										
50300285	FORM LINER TEXTURED SURFACE	SQ FT	2,356	2,356										
50500505	STUD SHEAR CONNECTORS	EACH	1,337	1,337										
50800105	REINFORCEMENT BARS	POUND	3,230	3,230										
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	20,140	20,140										
<del>50901750</del>	<del>PARAPET RAILING</del>	<del>FOOT</del>	<del>333</del>	<del>333</del>										
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	1	1										
54001002	BOX CULVERT END SECTIONS, CULVERT NO. 2	EACH	2	2										
54002070	EXPANSION BOLTS 3/4 INCH x 15 INCH	EACH	48	48										
54003000	CONCRETE BOX CULVERTS	CU YD	14	14										
<del>54010504</del>	<del>PRECAST CONCRETE BOX CULVERTS 5' x 4'</del>	<del>FOOT</del>	<del>22</del>	<del>22</del>										
<b>X5400903</b>	<b>PRECAST CONCRETE BOX CULVERTS 9' x 3' (SPECIAL)</b>	FOOT	168	168										
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 12"	EACH	1	1										
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1										
550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"	FOOT	1,676	1,676										
550A0070	STORM SEWERS, CLASS A, TYPE 1, 15"	FOOT	312	312										
550A0090	STORM SEWERS, CLASS A, TYPE 1, 18"	FOOT	129	129										
550A0120	STORM SEWERS, CLASS A, TYPE 1, 24"	FOOT	7	7										
550A0160	STORM SEWERS, CLASS A, TYPE 1, 36"	FOOT	115	115										
550A0340	STORM SEWERS, CLASS A, TYPE 2, 12"	FOOT	2,436	2,436										
550A0360	STORM SEWERS, CLASS A, TYPE 2, 15"	FOOT	1,054	1,054										
550A0380	STORM SEWERS, CLASS A, TYPE 2, 18"	FOOT	278	278										
550A0400	STORM SEWERS, CLASS A, TYPE 2, 21"	FOOT	239	239										
550A0410	STORM SEWERS, CLASS A, TYPE 2, 24"	FOOT	735	735										
550A0430	STORM SEWERS, CLASS A, TYPE 2, 30"	FOOT	733	733										
550A0450	STORM SEWERS, CLASS A, TYPE 2, 36"	FOOT	134	134										
550A4500	STORM SEWERS, CLASS A, TYPE 1, EQUIVALENT ROUND-SIZE, 36"	FOOT	159	159										
56100500	WATER MAIN, 4"	FOOT	5								5			
56100600	WATER MAIN, 6"	FOOT	222								222			
56100700	WATER MAIN, 8"	FOOT	2,354								2,354			
56100800	WATER MAIN, 10"	FOOT	1,695								1,695			
56100900	WATER MAIN, 12"	FOOT	1,002								1,002			
56104900	WATER VALVES, 6"	EACH	3								3			
56105000	WATER VALVES, 8"	EACH	9								9			

\* SPECIALTY ITEM

80% FED. SHARE SHALL UTILIZE CMAQ FUNDS #

Rev. 1-11-12

**CR & A**  
**CHRISTIAN-ROGE & ASSOCIATES, INC.**  
 ENGINEERS-PLANNERS-SURVEYORS  
 211 WEST WACKER DRIVE  
 CHICAGO, ILLINOIS 60606  
 1-312-372-2023 FAX: 1-312-372-5274

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
ILLINOIS ROUTE 64

SCALE: 1" = 50'  
DATE: OCTOBER 26, 2011

DRAWN BY B.K.  
CHECKED BY S.J.P.

FILE NAME = D:\62195-ah1-500.dgn  
 PLOT DATE = 10/26/2011  
 PLOT SCALE = 5/8" = 1' / IN.