

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE											
			URBAN	0003 ROADWAY IL. RTE. 64	0021 LIGHTING IL. RTE. 64	0021 T.S. AT 7TH AVE. 80% FED. 10% STATE 10% ST. CH	0021 T.S. AT TYLER 80% FED. 10% STATE 10% ST. CH	0021 T.S. AT DUNHAM 80% FED. 10% STATE 5% ST. CH 5% KANE	0021 INTER CONNECT 80% FED. 20% STATE #	0021 SIGNING	0043 WATER MAIN	0021		
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	80% FED. 20% STATE	100% ST. CHARLES					80% FED. 20% STATE	100% ST. CHARLES	100% ST. CHARLES		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5,057	5,057										
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	142	142										
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	467	467										
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	582	582										
* 78008200	POLYUREA PAVEMENT MARKING, TYPE I - LETTERS AND SYMBOLS	SQ FT	156	156										
* 78008210	POLYUREA PAVEMENT MARKING, TYPE I - LINE 4"	FOOT	2,278	2,278										
* 78008230	POLYUREA PAVEMENT MARKING, TYPE I - LINE 6"	FOOT	751	751										
* 78008250	POLYUREA PAVEMENT MARKING, TYPE I - LINE 12"	FOOT	70	70										
* 78008270	POLYUREA PAVEMENT MARKING, TYPE I - LINE 24"	FOOT	208	208										
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	734	734										
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	391	391										
78300100	PAVEMENT MARKING REMOVAL	SQ FT	6,205	6,205										
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	734	734										
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	2		2									
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1		1									
* 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	3			1	1	1						
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	8,212		105	255	969	910	2,416				***3,557	
* 81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	59				36	23						
* 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	4,213		4,060		64	89						
* 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	1,096				564	532						
* 81028250	UNDERGROUND CONDUIT, GALVANIZED STEEL, 5" DIA.	FOOT	170		170									
* 81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	515		515									
* 81400100	HANDHOLE	EACH	18			1	4	4	3				*** 6	
* 81400200	HEAVY-DUTY HANDHOLE	EACH	8				4	4						
* 81400300	DOUBLE HANDHOLE	EACH	4				2	2						
* 81603110	UNIT DUCT, 600V, 4-1/C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/2" DIA. POLYETHYLENE	FOOT	15,300		15,300									
* 81702180	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 3/0	FOOT	405		405									
* 81800410	AERIAL CABLE, 4-1/C NO. 4 WITH MESSENGER WIRE	FOOT	4,080		4,080									
* 82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	82		82									
* 82103310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 310 WATT	EACH	19		19									
* 83050760	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 8 FT. MAST ARM	EACH	1		1									
* 83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	79		79									
* 83050910	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 2-15 FT. MAST ARMS	EACH	1		1									
* 83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15 FT. MAST ARM	EACH	17		17									
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	567		567									
* 83057356	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH TWO 15 FT. MAST ARM	EACH	1		1									

* SPECIALTY ITEM

FOR INTERCONNECT ***

80% FED. SHARE SHALL UTILIZE CMAQ FUNDS #

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
ILLINOIS ROUTE 64

REVISIONS	
NAME	DATE

CR & A
CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
1-312-372-2023 FAX: 1-312-372-5274

SCALE: 1" = 50'
DATE: OCTOBER 26, 2011
DRAWN BY B.K.
CHECKED BY S.J.P.

Rev. 1-11-12