

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	129-R-2	KANE	243	14
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62195				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE										
			URBAN	0003 ROADWAY IL. RTE. 64	0021 LIGHTING IL. RTE. 64	0021 T.S. AT 7TH AVE. 80% FED. 10% STATE 10% ST. CH	0021 T.S. AT TYLER 80% FED. 10% STATE 10% ST. CH	0021 T.S. AT DUNHAM 80% FED. 10% STATE 5% ST. CH 5% KANE	0021 INTER CONNECT 80% FED. 20% STATE #	0021 SIGNING	0043 WATER MAIN	0021	
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	80% FED. 20% STATE	100% ST. CHARLES				80% FED. 20% STATE	100% ST. CHARLES	100% ST. CHARLES		
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	1,044	1,044									
Z0056610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	688	688									
Z0056612	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	246	246									
Z0056616	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	20	20									
Z0062456	TEMPORARY PAVEMENT	SQ YD	899	899									
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2										
Z0076600	TRAINEES	HOUR	1,000	1,000									
A2005020	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE) 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	20	20									
B2001620	TREE, CRATAEGUS CRUSGALLI INERMIS (THORNLESS COCKSPUR HAWTHORN) 2-1/2" CALIPER TREE FORM, BALLED AND BURLAPPED	EACH	6	6									
K0029634	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	2	2									
X5620126	WATER SERVICE LINE, SPECIAL	FOOT	750							750			
	WATER SERVICE LINE, LONG, 1" TO 2"	EACH	14							14			
XX000739	CURB STOP AND BOX, 1"	EACH	2							2			
XX006266	CURB STOP AND BOX, 1 1/2"	EACH	2							2			
X0324693	CURB STOP AND BOX, 2"	EACH	1							1			
XX006584	CURB STOP AND BOX TO BE REMOVED	EACH	18							18			
Z0067900	STEEL CASINGS 24"	FOOT	835							835			
X4420828	CLASS D PATCHES, TYPE III, 12 INCH (SPECIAL) PAVEMENT PATCHING	SQ YD	102							102			
		SQ YD	102							102			
X5610011	REMOVAL OF ASBESTOS WATER MAIN	FOOT	28							28			
X4420693	CLASS B PATCHES, SPECIAL, TYPE I, 13 INCH	SQ YD	4							4			
X4420742	CLASS C PATCHES, SPECIAL, TYPE II, 12 INCH	SQ YD	18							18			
X6026622	VALVE VAULTS TO BE REMOVED	EACH	11							11			
X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	3				1	1	1				
X9024100	TEMPORARY ACCESS WINTERIZE	SQ YD	500	500									

0042 SPECIALTY ITEM

80% FED. SHARE SHALL UTILIZE CMAQ FUNDS #

CR & A
CHRISTIAN-ROGE & ASSOCIATES, INC.
 ENGINEERS-PLANNERS-SURVEYORS
 211 WEST WACKER DRIVE
 CHICAGO, ILLINOIS 60606
 1-312-372-2023 FAX: 1-312-372-5274

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
ILLINOIS ROUTE 64

SCALE: 1" = 50'
DATE: OCTOBER 26, 2011

DRAWN BY B.K.
CHECKED BY S.J.P.

FILE NAME = D:\2195-ant-500.dgn
 PLOT DATE = 10/26/2011
 PLOT SCALE = 50.00000 0' / IN.

Rev. 1-11-12