

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE										
			URBAN	0003 ROADWAY IL. RTE. 64	0021 LIGHTING IL. RTE. 64	0021 T.S. AT 7TH AVE. 80% FED. 10% STATE 10% ST. CH	0021 T.S. AT TYLER 80% FED. 10% STATE 10% ST. CH	0021 T.S. AT DUNHAM 80% FED. 10% STATE 5% ST. CH 5% KANE	0021 INTER CONNECT 80% FED. 20% STATE #	0021 SIGNING 80% FED. 20% STATE	0043 WATER MAIN 100% ST. CHARLES	0021 100% ST. CHARLES	
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	80% FED. 20% STATE	100% ST. CHARLES								
60261540	INLETS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1	1									
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	7	7									
60500040	REMOVING MANHOLES	EACH	8	8									
60500050	REMOVING CATCH BASINS	EACH	1	1									
60500060	REMOVING INLETS	EACH	41	41									
60500105	FILLING MANHOLES	EACH	5	5									
60500205	FILLING CATCH BASINS	EACH	10	10									
60500305	FILLING INLETS	EACH	1	1									
60600605	CONCRETE CURB, TYPE B	FOOT	995	995									
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2,852	2,852									
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	9,050	9,050									
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	268	268									
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	13	13									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18	18									
67100100	MOBILIZATION	L SUM	1	1									
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	9,180	9,180									
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1									
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	10	10									
* 66901000	BACKFILL PLUGS	CU YD	25	25									
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	300	300									
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12									
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2,250	2,250									
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	489	489									
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	54,335	54,335									
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4,011	4,011									
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	665	665									
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	61,100	61,100									
* 72000100	SIGN PANEL - TYPE 1	SQ FT	382				12	35		335			
* 72000200	SIGN PANEL - TYPE 2	SQ FT	58				28	28					
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	13							13			
* 72900100	METAL POST - TYPE A	FOOT	347							347			
* 72900200	METAL POST - TYPE B	FOOT	156							156			
* 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	1							1			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,506	1,506									
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	20,596	20,596									

* SPECIALTY ITEM

80% FED. SHARE SHALL UTILIZE CMAQ FUNDS #

CR & A
CHRISTIAN-ROGE & ASSOCIATES, INC.
 ENGINEERS-PLANNERS-SURVEYORS
 211 WEST WACKER DRIVE
 CHICAGO, ILLINOIS 60606
 1-312-372-2023 FAX: 1-312-372-5274

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
ILLINOIS ROUTE 64

SCALE: 1" = 50'
DATE: OCTOBER 26, 2011

DRAWN BY B.K.
CHECKED BY S.J.P.

FILE NAME = D:\2195-ant-500.dgn
 PLOT DATE = 10/26/2011
 PLOT SCALE = 98.0000 sf / IN.