

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	129-R-2	KANE	243	12
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62195				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE											
			URBAN	0003 ROADWAY IL. RTE. 64	0021 LIGHTING IL. RTE. 64	0021 T.S. AT 7TH AVE. 80% FED. 10% STATE 10% ST. CH	0021 T.S. AT TYLER 80% FED. 10% STATE 10% ST. CH	0021 T.S. AT DUNHAM 80% FED. 10% STATE 5% ST. CH 5% KANE	0021 INTER CONNECT 80% FED. 20% STATE #	0021 SIGNING	0043 WATER MAIN	0021		
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	80% FED. 20% STATE	100% ST. CHARLES					80% FED. 20% STATE	100% ST. CHARLES	100% ST. CHARLES		
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	7					3	4					
* 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1						1					
* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	16					9	7					
* 88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4					2	2					
* 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1					1						
* 88055160	OPTICALLY PROGRAMMED SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	1						1					
* 88055200	OPTICALLY PROGRAMMED SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	3						3					
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	14					6	8					
* 88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1					1						
* 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	27					12	15					
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	27				7	9	11					
* 88600100	DETECTOR LOOP, TYPE I	FOOT	3,494				90	1,687	1,717					
* 88700200	LIGHT DETECTOR	EACH	2									2		
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1									1		
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	16					8	8					
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2					1	1					
* 89501400	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT	EACH	3									3		
* 89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	1									1		
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	6,090		6,090									
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2					1	1					
* 89502380	REMOVE EXISTING HANDHOLE	EACH	28				1	8	11	8				
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	19					11	8					
X0325751	DRIVING SOLDIER PILES	FOOT	563	563										
* X0325938	TEMPORARY WIRELESS INTERCONNECT, COMPLETE	L SUM	1						1					
* X0327004	TEMPORARY WOOD POLE, 60 FT., CLASS 4	EACH	2		2									
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	22	22										
X2800520	ABOVE GRADE INLET FILTERS	EACH	64	64										
X4020500	AGGREGATE SURFACE COURSE, TYPE B, 6"	SQ YD	80	80										
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	15	15										
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	54	54										
X4023000	TEMPORARY ACCESS (ROAD)	EACH	16	16										
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	319	319										
X5121800	PERMANENT STEEL SHEET PILING	SQ FT	1,290	1,290										
Δ X5537800	STORM SEWERS TO BE CLEANED, 12"	FOOT	1,059	1,059										
Δ X5537900	STORM SEWERS TO BE CLEANED, 15"	FOOT	215	215										

Δ NON-PARTICIPATING (100% STATE)  
\* SPECIALTY ITEM

80% FED. SHARE SHALL UTILIZE CMAQ FUNDS #



**CHRISTIAN-ROGE & ASSOCIATES, INC.**  
ENGINEERS-PLANNERS-SURVEYORS  
211 WEST WACKER DRIVE  
CHICAGO, ILLINOIS 60606  
1-312-372-2023 FAX: 1-312-372-5274

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**  
ILLINOIS ROUTE 64

SCALE: 1" = 50'  
DATE: OCTOBER 26, 2011

DRAWN BY B.K.  
CHECKED BY S.J.P.

FILE NAME = D:\62195\111-500.dgn  
PLOT DATE = 10/26/2011  
PLOT SCALE = 50.0000 # / IN.