

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	129-R-2	KANE	243	13
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62195				

NHF @ 14986,02 @ 14986,03 CMAQ NHF

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE											
CODE NO.	DESCRIPTION	UNIT	URBAN	0003 ROADWAY IL. RTE. 64	0021 LIGHTING IL. RTE. 64	0021 T.S. AT 7TH AVE. 80% FED. 10% STATE 10% ST. CH	0021 T.S. AT TYLER 80% FED. 10% STATE 10% ST. CH	0021 T.S. AT DUNHAM 80% FED. 10% STATE 5% ST. CH 5% KANE	0021 INTER CONNECT 80% FED. 20% STATE #	0021 SIGNING	0043 WATER MAIN	0021		
			TOTAL QUANTITIES	80% FED. 20% STATE	100% ST. CHARLES	100% ST. CHARLES	100% ST. CHARLES	100% ST. CHARLES	100% ST. CHARLES	80% FED. 20% STATE	100% ST. CHARLES	100% ST. CHARLES		
Δ X5538000	STORM SEWERS TO BE CLEANED, 18"	FOOT	25	25										
Δ X5538200	STORM SEWERS TO BE CLEANED, 24"	FOOT	384	384										
Δ X5538400	STORM SEWERS TO BE CLEANED, 30"	FOOT	77	77										
X6020096	MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	3	3										
X6026632	VALVE BOXES TO BE REMOVED	EACH	2								2			
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	24	24										
X6060052	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (SPECIAL)	FOOT	5,280	5,280										
X6064200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	782	782										
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1										
X7030025	WET REFLECTIVE TEMPORARY TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	214	214										
X7030030	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	13,552	13,552										
X7030040	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 6 INCH	FOOT	504	504										
X7030050	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 12 INCH	FOOT	174	174										
X7030055	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	174	174										
* X8250505	LIGHTING CONTROLLER, SPECIAL	EACH	2		2									
* X8570225	FULL-ACTUATED CONTROLLER AND CABINET, TYPE IV, SPECIAL	EACH	2				1	1						
* X8570230	FULL-ACTUATED CONTROLLER AND CABINET, TYPE V, SPECIAL	EACH	1						1					
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	1,347										1,347	
Z0001050	AGGREGATE SUBGRADE, 12"	SQ YD	29,000	29,000										
<del>Z0001070</del>	<del>AGGREGATE SUBGRADE, SPECIAL</del>	<del>SQ YD</del>	<del>11,340</del>	<del>11,340</del>										
Z0004538	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 10"	SQ YD	17								17			
Δ Z0005300	BOX CULVERTS TO BE CLEANED	EACH	2	2										
* Z0007118	UNTREATED TIMBER LAGGING	SQ FT	929	929										
Z0007430	TEMPORARY SIDEWALK	SQ FT	500	500										
Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	350	350										
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1										
Z0026402	FURNISHING SOLDIER PILES (HP SECTION)	FOOT	563	563										
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	839	839										
* Z0033020	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	94		94									
* Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	18		18									
* Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	2						2					
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1,500	1,500										
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES, 4"	FOOT	246	246										
Z0048400	RAILROAD CROSSING REMOVAL	EACH	1	1										

Δ NON-PARTICIPATING (100% STATE)  
\* SPECIALTY ITEM

80% FED. SHARE SHALL UTILIZE CMAQ FUNDS #

CMAQ ●

Rev.

FILE NAME = D:\52195\111-5010.dgn  
PLOT DATE = 10/26/2011  
PLOT SCALE = 50.0000 # / IN.

**CR & A**  
CHRISTIAN-ROGE & ASSOCIATES, INC.  
ENGINEERS-PLANNERS-SURVEYORS  
211 WEST WACKER DRIVE  
CHICAGO, ILLINOIS 60606  
1-312-372-2023 FAX: 1-312-372-5274

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
ILLINOIS ROUTE 64

SCALE: 1" = 50'  
DATE: OCTOBER 26, 2011

DRAWN BY B.K.  
CHECKED BY S.J.P.