

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE											
			URBAN	0003 ROADWAY IL. RTE. 64	0021 LIGHTING IL. RTE. 64	0021 T.S. AT 7TH AVE. 80% FED. 10% STATE 10% ST. CH	0021 T.S. AT TYLER 80% FED. 10% STATE 10% ST. CH	0021 T.S. AT DUNHAM 80% FED. 10% STATE 5% ST. CH 5% KANE	0021 INTER CONNECT 80% FED. 20% STATE #	0021 SIGNING	0043 WATER MAIN	0021		
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	80% FED. 20% STATE	100% ST. CHARLES					80% FED. 20% STATE	100% ST. CHARLES	100% ST. CHARLES		
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	1,044	1,044										
Z0056610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	688	688										
Z0056612	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	246	246										
Z0056616	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	20	20										
Z0062456	TEMPORARY PAVEMENT	SQ YD	899	899										
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2				1	1						
Z0076600	TRAINEES	HOUR	1,000	1,000										
A2005020	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE) 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	20	20										
B2001620	TREE, CRATAEGUS CRUSGALLI INERMIS (THORNLESS COCKSPUR HAWTHORN) 2-1/2" CALIPER TREE FORM, BALLED AND BURLAPPED	EACH	6	6										
K0029634	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	2	2										
X5620126	WATER SERVICE LINE, SPECIAL	FOOT	750								750			
	WATER SERVICE LINE, LONG, 1" TO 2"	EACH	14								14			
XX000739	CURB STOP AND BOX, 1"	EACH	2								2			
XX006266	CURB STOP AND BOX, 1 1/2"	EACH	2								2			
X0324693	CURB STOP AND BOX, 2"	EACH	1								1			
XX006584	CURB STOP AND BOX TO BE REMOVED	EACH	18								18			
Z0067900	STEEL CASINGS 24"	FOOT	835								835			
X4420828	CLASS D PATCHES, TYPE III, 12 INCH (SPECIAL) PAVEMENT PATCHING	SQ YD	102								102			
		SQ YD	102								102			
X5610011	REMOVAL OF ASBESTOS WATER MAIN	FOOT	28								28			
X4420693	CLASS B PATCHES, SPECIAL, TYPE I, 13 INCH	SQ YD	4								4			
X4420742	CLASS C PATCHES, SPECIAL, TYPE II, 12 INCH	SQ YD	18								18			
X6026622	VALVE VAULTS TO BE REMOVED	EACH	11								11			
X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	3			1	1	1						

0 0042
* SPECIALTY ITEM

80% FED. SHARE SHALL UTILIZE CMAQ FUNDS #

CR & A
CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
1-312-372-2023 FAX: 1-312-372-5274

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
ILLINOIS ROUTE 64

SCALE: 1" = 50'
DATE: OCTOBER 26, 2011

DRAWN BY B.K.
CHECKED BY S.J.P.