

SUMMARY OF QUANTITIES				0004 ROADWAY SKOKIE 70% STU 15% STATE (RECON-STRUCTION)	0004 ROADWAY SKOKIE 70% STU 30% STATE (REHAB.-STA. 127+31.09 TO 135+97)	0004 ROADWAY SKOKIE 100% STATE (RESURF-STA. 120+50 TO 127+31.09)	0043 ROADWAY IN-LINE DETENTION 70% STU 30% LA	0021 LIGHTING SKOKIE 70% STU 30% LA	0021 SIGNALS SOUTH MALL ENTRANCE 70% STU 30% STATE	0021 SIGNALS MIDDLE MALL ENTRANCE 70% STU 30% STATE	0021 SIGNALS NORTH MALL ENTRANCE 70% STU 30% STATE	0021 SIGNALS OLD ORCHARD 70% STU 15% STATE 15% LA	0021 SIGNALS INTERCONNECT 70% STU 30% STATE	0043 WATER, SIDEWALK & ITEMS SKOKIE NON-PART 100% LA	0021 SIGNALS EMERGENCY VEHICLE PREEMPTION 100% LA
CODE NO	PAY ITEM	UNIT	QUANTITY												
20100110	• TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	62	44	18										
20101000	TEMPORARY FENCE	FOOT	3,280	1,440	1,040	800									
20101200	• TREE ROOT PRUNING	EACH	82	36	26	20									
20101300	• TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	61	22	20	19									
20101350	• TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	21	14	6	1									
20200100	EARTH EXCAVATION	CU YD	5,712	4,556	926	63								167	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	3,084	2,551	275									258	
20800150	TRENCH BACKFILL	CU YD	7,076	409	341	91	4,735							1,500	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1,605	1,509	96										
21101615	• TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4,704	2,172	1,522	1,010									
21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	200	200											
25000400	• NITROGEN FERTILIZER NUTRIENT	POUND	59	27	19	13									
25000500	• PHOSPHORUS FERTILIZER NUTRIENT	POUND	59	27	19	13									
25000600	• POTASSIUM FERTILIZER NUTRIENT	POUND	59	27	19	13									
25200110	• SODDING, SALT TOLERANT	SQ YD	4,704	2,172	1,522	1,010									
25200200	• SUPPLEMENTAL WATERING	UNIT	15	7	5	3									
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	108	57	32	19									
28000510	INLET FILTERS	EACH	93	65	24	4									
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	3,623	1,056	760	1,126								681	
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	9,972	9,012	960										
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	11,078	11,078											
35301200	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	2,763	2,763											
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SQ YD	1,116	508	608										
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5,598	2,901	1,496	1,201									
40600300	AGGREGATE (PRIME COAT)	TON	113	58	30	25									
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	468		170	298									
40600895	CONSTRUCTING TEST STRIP	EACH	2	2											
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	76			76									
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	86											86	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	48	48											
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	3,343	1,806	1,537										
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	12	12											
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2,730	1,407	734	589									
42001300	PROTECTIVE COAT	SQ YD	6,497	3,306	1,321	1,190								680	

• SPECIALTY ITEM