SUMMARY OF QUANTITIES				0004 ROADWAY SKOKIE 70% STU 15% STATE 15% LA (RECON-STRUCTION)	0004 ROADWAY SKOKIE 70% STU 30% STATE (REHAB.- STA. 127+31.09 TO 135+97)	0004 ROADWAY SKOKIE 100% STATE (RESURF- STA. 120+50 TO 127+31.09)	0043 ROADWAY IN-LINE DETENTION 70% STU 30% LA	0021 LIGHTING SKOKIE 70% STU 30% LA	0021 SIGNALS SOUTH MALL ENTRANCE 70% STU 30% STATE	0021 SIGNALS MIDDLE MALL ENTRANCE 70% STU 30% STATE	0021 SIGNALS NORTH MALL ENTRANCE 70% STU 30% STATE	0021 SIGNALS OLD ORCHARD 70% STU 15% STATE 15% LA	0021 SIGNALS INTERCONNECT 70% STU 30% STATE	0043 WATER, SIDEWALK & ITEMS SKOKIE NON-PART 100% LA	0021 SIGNALS EMERGENCY VEHICLE PREEMPTION 100% LA
CODE NO	PAY ITEM	UNIT	QUANTITY												
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	118	118											
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	22,249	6,443	4,667	5,066								6,073	
42400800	DETECTABLE WARNINGS	SQ FT	298	210										88	
44000100	PAVEMENT REMOVAL	SQ YD	18,328	16,714	1,285	329									
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	4,108			4,108									
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	314	271	43										
44000300	CURB REMOVAL	FOOT	233	197	36										
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	9,121	5,008	2,826	1,287									
44000600	SIDEWALK REMOVAL	SQ FT	14,889	5,546	4,277	5,066									
44002220	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5"	SQ YD	317											317	
44003100	MEDIAN REMOVAL	SQ FT	16,475	13,527	1,269	1,679									
44201337	CLASS C PATCHES, TYPE I, 9 INCH	SQ YD	4		4										
44201341	CLASS C PATCHES, TYPE II, 9 INCH	SQ YD	39		11									28	
44201345	CLASS C PATCHES, TYPE III, 9 INCH	SQ YD	89		53	36									
44201347	CLASS C PATCHES, TYPE IV, 9 INCH	SQ YD	4,426		453	81	2,307							1,585	
50102400	CONCRETE REMOVAL	CU YD	6	6											
550A0830	STORM SEWERS, CLASS A, TYPE 3 78"	FOOT	234				234								
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	1,234	825	329	80									
550A2330	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15"	FOOT	91			91									
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	461	203	258										
550A2530	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 15"	FOOT	161		122	39									
550A2540	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 18"	FOOT	18		18										
550A2640	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 60"	FOOT	62	62											
550A2660	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 72"	FOOT	1,504				1,504								
550A5300	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 36"	FOOT	32				32								
55100200	STORM SEWER REMOVAL 6"	FOOT	12		12										
55100300	STORM SEWER REMOVAL 8"	FOOT	239	14	158	67									
55100400	STORM SEWER REMOVAL 10"	FOOT	47		11	36									
55100500	STORM SEWER REMOVAL 12"	FOOT	135	135											
55100700	STORM SEWER REMOVAL 15"	FOOT	47	47											
* 56100200	WATER MAIN 1 1/2"	FOOT	18											18	
* 56100600	WATER MAIN 6"	FOOT	334											334	
* 56100700	WATER MAIN 8"	FOOT	47											47	
* 56100900	WATER MAIN 12"	FOOT	2,781											2,781	

• SPECIALTY ITEM

TranSystems
1475 EAST WOODFIELD ROAD, SUITE 600
SCHAUMBURG, ILLINOIS 60173
(847) 605-9600