



1475 EAST WOODFIELD ROAD, SUITE 600
SCHALMUR, ILLINOIS 60173
(847) 605-9600

SUMMARY OF QUANTITIES				0004 ROADWAY SKOKIE 70% STU 15% LA (RECONSTRUCTION)	0004 ROADWAY SKOKIE 70% STU 30% STATE (REHAB.- STA. 127+31.09 TO 135+97)	0004 ROADWAY SKOKIE 100% STATE (RESURF- STA. 120+50 TO 127+31.09)	0043 ROADWAY IN-LINE DETENTION 70% STU 30% LA	0021 LIGHTING SKOKIE 70% STU 30% LA	0021 SIGNALS SOUTH MALL ENTRANCE 70% STU 30% STATE	0021 SIGNALS MIDDLE MALL ENTRANCE 70% STU 30% STATE	0021 SIGNALS NORTH MALL ENTRANCE 70% STU 30% STATE	0021 SIGNALS OLD ORCHARD 70% STU 15% LA	0021 SIGNALS INTERCONNECT 70% STU 30% STATE	0043 WATER, SIDEWALK & ITEMS SKOKIE NON-PART 100% LA	0021 SIGNALS EMERGENCY VEHICLE PREEMPTION 100% LA
CODE NO	PAY ITEM	UNIT	QUANTITY												
7800650	• THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	98	98											
78008200	• POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SO FT	473	255	109	109									
78008210	• POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	8,577	4,234	3,719	624									
78008230	• POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	3,056	1,827	149	1,080									
78008240	• POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	1,505	838	667										
78008250	• POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	412	248	164										
78008270	• POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	729	330	181	218									
78100100	• RAISED REFLECTIVE PAVEMENT MARKER	EACH	382	215	82	85									
78300100	PAVEMENT MARKING REMOVAL	SO FT	274	173	57	44									
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	350	350											
80400100	• ELECTRIC SERVICE INSTALLATION	EACH	1					1							
80400200	• ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1					1							
80500010	• SERVICE INSTALLATION - GROUND MOUNTED	EACH	1									1			
81028200	• UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	3,040					1,148		313	614	965			
81028210	• UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	161								126	35			
81028220	• UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	63								19	44			
81028240	• UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	1,213					326			342	545			
81400100	• HANDHOLE	EACH	10							1	4	5			
81400200	• HEAVY-DUTY HANDHOLE	EACH	6							1	1	4			
81400300	• DOUBLE HANDHOLE	EACH	3								1	2			
81603040	• UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	500					500							
81603090	• UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	7,700					7,700							
81702180	• ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 3/0	FOOT	600					600							
81800320	• AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	1,600					1,600							
83009600	• LIGHT POLE, ALUMINUM, 45 FT. M.H., 15 FT. MAST ARM	EACH	35					35							
83600200	• LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	350					350							
84200500	• REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	30					30							
84200804	• REMOVAL OF POLE FOUNDATION	EACH	30					30							
84500110	• REMOVAL OF LIGHTING CONTROLLER	EACH	1					1							
85000200	• MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1						1						
86200120	• UNINTERRUPTABLE POWER SUPPLY, EXTENDED	EACH	4						1	1	1	1			
86400100	• TRANSCEIVER - FIBER OPTIC	EACH	2										2		
87100160	• FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 24F	FOOT	2,083										2,083		
87300925	• ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	1,219										1,219		

• SPECIALTY ITEM