



1475 EAST WOODFIELD ROAD, SUITE 600
SCHALMUR, ILLINOIS 60173
(847) 605-9600

SUMMARY OF QUANTITIES				0004 ROADWAY SKOKIE 70% STU 15% STATE 15% LA (RECONSTRUCTION)	0004 ROADWAY SKOKIE 70% STU 30% STATE (REHAB.- STA. 127+31.09 TO 135+97)	0004 ROADWAY SKOKIE 100% STATE (RESURF- STA. 120+50 TO 127+31.09)	0043 ROADWAY IN-LINE DETENTION 70% STU 30% LA	0021 LIGHTING SKOKIE 70% STU 30% LA	0021 SIGNALS SOUTH MALL ENTRANCE 70% STU 30% STATE	0021 SIGNALS MIDDLE MALL ENTRANCE 70% STU 30% STATE	0021 SIGNALS NORTH MALL ENTRANCE 70% STU 30% STATE	0021 SIGNALS OLD ORCHARD 70% STU 15% STATE 15% LA	0021 SIGNALS INTERCONNECT 70% STU 30% STATE	0043 WATER, SIDEWALK & ITEMS SKOKIE NON-PART 100% LA	0021 SIGNALS EMERGENCY VEHICLE PREEMPTION 100% LA
CODE NO	PAY ITEM	UNIT	QUANTITY												
87301215	• ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,548									1,548			
87301225	• ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	3,806						376	531	398	2,501			
87301245	• ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	7,631						422	386	2,955	3,868			
87301255	• ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	666									666			
87301305	• ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	5,550							789	1,237	3,524			
87301805	• ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	213								28	185			
87301900	• ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1,328								559	769			
87502440	• TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1									1			
87502480	• TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	3								3				
87502520	• TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	2							1	1				
87700250	• STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1								1				
87702810	• STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 16 FT.	EACH	2									2			
87702900	• STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 34 FT.	EACH	1									1			
87702930	• STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 40 FT.	EACH	1									1			
87702990	• STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 54 FT.	EACH	1									1			
87704425	• STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 40 FT. AND 46 FT.	EACH	1								1				
87704558	• STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 58 FT. AND 20 FT.	EACH	1									1			
87800100	• CONCRETE FOUNDATION, TYPE A	FOOT	20								16	4			
87800150	• CONCRETE FOUNDATION, TYPE C	FOOT	8								4	4			
87800400	• CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	20									20			
87800415	• CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	66								27	39			
87800420	• CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	21									21			
87900200	• DRILL EXISTING HANDHOLE	EACH	3							2	1				
88030020	• SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	40						8	8	9	15			
88030050	• SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	7							4	3				
88030110	• SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	8						4			4			
88030210	• SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	7						2	2	2	1			
88030220	• SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2						2						
88102717	• PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4						2			2			
88102747	• PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4						1			3			
88200210	• TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	48						12	8	9	19			
88500100	• INDUCTIVE LOOP DETECTOR	EACH	20								5	15			
88600100	• DETECTOR LOOP, TYPE I	FOOT	745						111	286	348				
88600700	• PREFORMED DETECTOR LOOP	FOOT	1,277								117	1,160			

• SPECIALTY ITEM

FILE NAME = g:\ch\88\0243\Road\Sheet\045-6-104-SumQty.dwg	USER NAME = CEComin	DESIGNED CEC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	U.S. ROUTE 41 (SKOKIE BOULEVARD) SUMMARY OF QUANTITIES			F.A.P. RTE. 350	SECTION 00-00243-00-CH	COUNTY COOK	TOTAL SHEETS 142	SHEET NO. 9
PLOT SCALE = 500.0000 ' / IN.	CHECKED DWB	DRAWN CEC	REVISED -		SCALE: NONE	SHEET NO. 6 OF 8 SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT				
PLOT DATE = 10/26/2011	DATE 10/26/2011	REVISOR	REVISION									
CONTRACT NO. 63566												