SUMMARY OF QUANTITIES				0004 ROADWAY SKOKIE 70% STU 15% STATE 15% LA (RECON-STRUCTION)	0004 ROADWAY SKOKIE 70% STU 30% STATE (REHAB.- STA. 127+31.09 TO 135+97)	0004 ROADWAY SKOKIE 100% STATE (RESURF- STA. 120+50 TO 127+31.09)	0043 ROADWAY IN-LINE DETENTION 70% STU 30% LA	0021 LIGHTING SKOKIE 70% STU 30% LA	0021 SIGNALS SOUTH MALL ENTRANCE 70% STU 30% STATE	0021 SIGNALS MIDDLE MALL ENTRANCE 70% STU 30% STATE	0021 SIGNALS NORTH MALL ENTRANCE 70% STU 30% STATE	0021 SIGNALS OLD ORCHARD 70% STU 15% STATE 15% LA	0021 SIGNALS INTERCONNECT 70% STU 30% STATE	0043 WATER, SIDEWALK & ITEMS SKOKIE NON-PART 100% LA	0021 SIGNALS EMERGENCY VEHICLE PREEMPTION 100% LA
CODE NO	PAY ITEM	UNIT	QUANTITY												
88700200	• LIGHT DETECTOR	EACH	10												10
88700300	• LIGHT DETECTOR AMPLIFIER	EACH	4												4
88800100	• PEDESTRIAN PUSH-BUTTON	EACH	8									8			
89000100	• TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	3							1	1	1			
89502215	• MODIFY EXISTING CONTROLLER FOUNDATION	EACH	2						1	1					
89502300	• REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	2,471							464			2,007		
89502375	• REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	4						1	1	1	1			
89502380	• REMOVE EXISTING HANDHOLE	EACH	30							2	10	18			
89502385	• REMOVE EXISTING CONCRETE FOUNDATION	EACH	22								7	15			
A2005016	• TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2" CALIPER, BALLED AND BURLAPPED	EACH	3	3											
A2008518	• TREE, ULMUS MORTON GLOSSY (TRIUMPH ELM), 2" CALIPER, BALLED AND BURLAPPED	EACH	15	2	13										
B2005716	• TREE, PYRUS CALLERYANA CHANTICLEER (CHANTICLEER CALLERY PEAR), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	2	2											
X0324907	• TEMPORARY MAST ARM 15 FT.	EACH	6					6							
X0326148	• TEMPORARY WOOD POLE, 60 FT., CLASS 4, 15 FT. MAST ARM	EACH	1					1							
X0327236	• TEMPORARY WOOD POLE, 50 FT., CLASS 4	EACH	1					1							
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	4	4											
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	10	9	1										
X4023000	TEMPORARY ACCESS (ROAD)	EACH	2	2											
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	8,792		6,944	1,848									
X5630006	• CUT AND CAP EXISTING 6" WATER MAIN	EACH	12											12	
X5630008	• CUT AND CAP EXISTING 8" WATER MAIN	EACH	2											2	
X5630012	• CUT AND CAP EXISTING 12" WATER MAIN	EACH	2											2	
X5630706	• CONNECTION TO EXISTING WATER MAIN 6"	EACH	6											6	
X5630708	• CONNECTION TO EXISTING WATER MAIN 8"	EACH	2											2	
X5630712	• CONNECTION TO EXISTING WATER MAIN 12"	EACH	3											3	
X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	20	13	5	2									
X6026051	SANITARY MANHOLES TO BE RECONSTRUCTED	EACH	1	1											
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	8		3	4	1								
X6061005	CONCRETE CURB, TYPE B (SPECIAL)	FOOT	151	151											
X6064200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	2,814		2,814										
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1											
X8140115	* HANDHOLE TO BE ADJUSTED	EACH	4							4					
X8210451	• LUMINAIRE, STREET LIGHTING, HIGH PRESSURE SODIUM VAPOR, 400 WATT, 240 VOLT	EACH	41					41							
X8250505	• LIGHTING CONTROLLER, SPECIAL	EACH	1					1							

• SPECIALTY ITEM

TranSystems
1475 EAST WOODFIELD ROAD, SUITE 600
SCHAUMBURG, ILLINOIS 60173
(847) 605-9600

FILE NAME = g:\CH88\IM45\Road\Sheets\IM45-6-1M4-SumQty.sht	USER NAME = CEComin	DESIGNED CEC	REVISED -
		DRAWN CEC	REVISED -
	PLOT SCALE = 50.000 ' / IN.	CHECKED DWB	REVISED -
	PLOT DATE = 11/4/2011	DATE 11/07/2011	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 41 (SKOKIE BOULEVARD)
SUMMARY OF QUANTITIES

SCALE: NONE | SHEET NO. 7 OF 8 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	00-00243-00-CH	COOK	142	10
		CONTRACT NO. 63566		
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT		