SUMMARY OF QUANTITIES				0004 ROADWAY SKOKIE 70% STU 15% STATE 15% LA (RECON-STRUCTION)	0004 ROADWAY SKOKIE 70% STU 30% STATE (REHAB.- STA. 127+31.09 TO 135+97)	0004 ROADWAY SKOKIE 100% STATE (RESURF- STA. 120+50 TO 127+31.09)	0043 ROADWAY IN-LINE DETENTION 70% STU 30% LA	0021 LIGHTING SKOKIE 70% STU 30% LA	0021 SIGNALS SOUTH MALL ENTRANCE 70% STU 30% STATE	0021 SIGNALS MIDDLE MALL ENTRANCE 70% STU 30% STATE	0021 SIGNALS NORTH MALL ENTRANCE 70% STU 30% STATE	0021 SIGNALS OLD ORCHARD 70% STU 15% STATE 15% LA	0021 SIGNALS INTERCONNECT 70% STU 30% STATE	0043 WATER, SIDEWALK & ITEMS SKOKIE NON-PART 100% LA	0021 SIGNALS EMERGENCY VEHICLE PREEMPTION 100% LA
CODE NO	PAY ITEM	UNIT	QUANTITY												
X8360215	• LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	50					50							
X8570225	• FULL-ACTUATED CONTROLLER AND CABINET, TYPE IV, SPECIAL	EACH	2								1	1			
X8730250	• ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	2,258												2,258
X8900010	• TEMPORARY TRAFFIC SIGNAL INTERCONNECT	EACH	1										1		
XX002112	TEMPORARY LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	7					7							
XX002118	STORM SEWER DUCTILE IRON 12"	FOOT	718	321	397										
XX002948	TEMPORARY ACCESS WALK	EACH	20	20											
XX003668	PRECONSTRUCTION VIDEO TAPING	L SUM	1	1											
XX008504	PRECAST "T" MANHOLES FOR 78" DIAMETER STORM SEWER, TYPE 1 FRAME, CLOSED LID	EACH	1				1								
XX008541	PRECAST "T" MANHOLES FOR 72" DIAMETER STORM SEWER, TYPE 1 FRAME, CLOSED LID	EACH	5				5								
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	7,400	7,400											
Z0004538	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 10"	SQ YD	169	156	13										
Z0004910	HOT-MIX ASPHALT FOR PATCHING POTHOLES (HOT MIX)	TON	10	10											
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1											
Z0019600	DUST CONTROL WATERING	UNIT	100	100											
Z0023202	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	182	130	52										
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	262	262											
Z0033020	• LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	41					41							
Z0033028	• MAINTENANCE OF LIGHTING SYSTEM	CAL MO	15					15							
Z0033046	• RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1										1		
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1,274	1,274											
Z0062456	TEMPORARY PAVEMENT	SQ YD	7,134	5,667	1,280	187									
Z0073510	• TEMPORARY TRAFFIC SIGNAL TIMING	EACH	3							1	1	1			
Z0076600	•• TRAINEES	HOUR	1,500	1,500											
LR442020	BITUMINOUS PATCHING MIXTURE (GROUP II)	TON	10	10											
TOTAL															

•• TRAINEES CONSTRUCTION TYPE CODE = 0042

• SPECIALTY ITEM

TranSystems
1475 EAST WOODFIELD ROAD, SUITE 600
SCHAUMBURG, ILLINOIS 60173
(847) 605-9600

FILE NAME = g:\CHB3\0045\Road\Sheets\0045-G-104-Sum0ty.sht	USER NAME = CEComin	DESIGNED CEC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	U.S. ROUTE 41 (SKOKIE BOULEVARD) SUMMARY OF QUANTITIES	F.A.P. RTE. 350	SECTION 00-00243-00-CH	COUNTY COOK / TOTAL SHEETS 142 / SHEET NO. 11
		DRAWN CEC	REVISED -					CONTRACT NO. 63566
	PLOT SCALE = 50.000 ' / IN.	CHECKED DWB	REVISED -					
	PLOT DATE = 11/4/2011	DATE 11/07/2011	REVISED -		SCALE: NONE / SHEET NO. 8 OF 8 SHEETS / STA. TO STA.	FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT