

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	0004	0021	0042
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	1		
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	381	381		
55100500	STORM SEWER REMOVAL 12"	FOOT	158	158		
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	496	496		
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	6	6		
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	9	9		
60260100	INLETS TO BE ADJUSTED	EACH	2	2		
60500050	REMOVING CATCH BASINS	EACH	2	2		
60500060	REMOVING INLETS	EACH	4	4		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	450	450		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2049	2049		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	2248	2248		
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	1597	1597		
* 60625900	P.C.C. RAMPED MEDIAN TERMINAL	EACH	4	4		
** 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	62.5		62.5	
** 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1		1	
** * 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1		1	
63200310	GUARDRAIL REMOVAL	FOOT	95		95	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4		
67100100	MOBILIZATION	LSUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60		60	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4		4	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	844		844	
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	594		594	
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	10644		10644	
70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	1022		1022	
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	1226		1226	
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	192		192	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5854		5854	
*** 72000100	SIGN PANEL - TYPE I	SQ FT	220		220	
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	7		7	
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	2		2	
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	569		569	
73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	42		42	
** 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	454		454	
** 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7327		7327	
** 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2916		2916	
** 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	591		591	
** 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1026		1026	
** 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	230		230	
** 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1058		1058	
** 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	116		116	

* SEE SPECIAL PROVISIONS
** DENOTES SPECIALTY ITEMS, SEE SPECIAL PROVISIONS
*** INCLUDES SIGNAL QUANTITIES

PLANNING, DESIGN, CONSTRUCTION, MAINTENANCE, AND OPERATIONS
ILLINOIS DEPARTMENT OF TRANSPORTATION
CONTRACT NO. 63597
DATE: 11/8/2011

SEC Group, Inc.
1848 Professional Design Firm # 184-000109
An HCSS Group Company
223 Adams Drive
New Lenox, Illinois 80451
1-815-462-2244 / 1-815-462-2222
www.secgroupinc.com
*Member of the HCSS Group - New Lenox, IL - Chicago, IL

USER NAME = RBest
PLOT SCALE = NONE
PLOT DATE = 11/8/2011

DESIGNED - BDC
DRAWN - RCB
CHECKED - APS
DATE - 11/8/11

REVISED - Δ 1-10-12
REVISED -
REVISED -
REVISED -

**ILLINOIS DEPARTMENT OF TRANSPORTATION
PROPOSED ROADWAY IMPROVEMENTS
C.H. 52 (GOUGAR ROAD) AT U.S. ROUTE 30**

SUMMARY OF QUANTITIES

SCALE:	NONE	SHEET NO. 2 OF 4 SHEETS	STA.	TO STA.
--------	------	-------------------------	------	---------

F.A.U. RTE.	SECTION NO.	COUNTY	TOTAL SHEETS	SHEET NO.
367	07-00154-11-TL	WILL	70	5
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 63597	