



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 12, 2012

SUBJECT: FAU 2836 (Orchard Drive)  
Project M-8003(661)  
Section 06-00090-00-FP (Park Forest)  
Cook County  
Contract No. 63635  
Item 125  
January 20, 2012 Letting  
Addendum (A)

## NOTICE TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

- 1. Index of Special Provisions.**
- 2. Page 19 of the Special Provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott Stitt, P.E.  
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger, P.E.", with the initials "P.E." written in a smaller font to the right of the signature.

By: Ted B. Walschleger, P.E.  
Engineer of Project Management

**INDEX OF SPECIAL PROVISIONS**

	<b><u>PAGE NO.</u></b>
LOCATION OF PROJECT .....	1
DESCRIPTION OF WORK.....	1
COMPLETION DATE PLUS WORKING DAYS.....	1
MAINTENANCE OF ROADWAYS .....	2
STATUS OF UTILITIES TO BE ADJUSTED .....	2
ADJUSTING WATER MAIN .....	4
FIRE HYDRANTS TO BE ADJUSTED.....	4
ADJUSTMENTS AND RECONSTRUCTIONS .....	5
DRAINAGE AND INLET PROTECTION UNDER TRAFFIC (DISTRICT 1).....	6
TRAFFIC CONTROL PLAN .....	8
GENERAL ELECTRICAL REQUIREMENTS .....	9
ELECTRIC SERVICE INSTALLATION FOR LIGHTING WORK .....	9
ELECTRICAL UTILITY SERVICE CONNECTION .....	10
UNDERGROUND RACEWAYS .....	11
UNIT DUCT .....	11
LUMINAIRE, HIGH PRESSURE SODIUM, HORIZONTAL MOUNT, 250 WATT .....	12
LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 100AMP .....	14
REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE.....	14
RELOCATE EXISTING LIGHTING UNIT .....	14
ILLUMINATED SIGN, LED.....	15
REMOVE EXISTING HANDHOLE .....	16
REMOVE EXISTING CONCRETE FOUNDATION.....	17
AGGREGATE SUBGRADE, 12" .....	17
CLEANING EXISTING DRAINAGE STRUCTURES.....	19
STORM SEWERS TO BE CLEANED .....	19
FENCE REMOVAL .....	19
TEMPORARY INFORMATION SIGNING.....	20
PORTLAND CEMENT CONCRETE SURFACE REMOVAL 2 1/4" .....	21
POROUS GRANULAR EMBANKMENT, SUBGRADE .....	22
STORM SEWER ADJACENT TO OR CROSSING WATER MAIN.....	23

Revised 1/11/12

Measured Quantities. Aggregate subgrade will be measured in place and the area computed in square yards (square meters).

Basis of Payment. This work will be paid for at the contract unit price per square yard (square meter) for AGGREGATE SUBGRADE, 12".

**CLEANING EXISTING DRAINAGE STRUCTURES:**

All existing manholes, catch basins and inlets shall be considered as drainage structures insofar as the interpretation of this Special Provision is concerned.

All existing drainage structures which are to be adjusted or reconstructed shall be cleaned in accordance with Article 602.15 of the Standard Specifications. This work will be paid for in accordance with Article 602.16 of the Standard Specifications.

All other existing drainage structures which are to be left in place within the specified project limits of Sauk Trail to U.S. Route 30 will be cleaned according to Article 602.15 of the Standard Specifications.

Basis of Payment. This work will be paid for at the contract unit price per each for DRAINAGE STRUCTURES TO BE CLEANED.

**STORM SEWERS TO BE CLEANED:**

Work shall be according to Section 550, except as modified herein:

550.01 Description. Add the following to the end of this Article:

"This work shall consist of cleaning existing storm sewers including the removal and satisfactory disposal of material resulting from the cleaning."

550.04 Excavation and Foundation. Add the following paragraph to the end of this Article:

"The existing storm sewer shall be cleaned of debris. Debris shall be removed and satisfactorily disposed of.

The contractor shall coordinate cleaning with the Village and the Illinois Department of Transportation."

550.10 Basis of Payment. Add the following to the end of this Article:

"This work will be paid for at the contract unit price per foot for STORM SEWERS TO BE CLEANED of the diameter specified."

**FENCE REMOVAL:**

This work shall be done in accordance with the applicable portions of Section 664 of the Standard Specifications except as modified herein:

664.03 General. Add the following to the end of the Article:

"Fence shall be removed as indicated in the plans or as determined by the Engineer. Removal shall include the removal of any appurtenances atop the fence and the complete removal of concrete post foundations. Special care shall be taken to protect fence to remain."

664.12 Method of Measurement. Add the following to the end of the Article:

"Fence removal will be measured for payment in feet of fence removed, regardless of height, type or depth below grade."

664.13 Basis of Payment. Add the following to the end of the Article: