

SUMMARY OF QUANTITIES				STU Funding 70% Federal, 30% Local		
				CONSTRUCTION TYPE CODE		
				0004	0021	0040
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	TRAFFIC SIGNALS & LIGHTING	BRIDGE & RETAINING WALL
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	465	465	-	-
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	655	655	-	-
20101000	TEMPORARY FENCE	FOOT	250	-	-	250
20101100	TREE TRUNK PROTECTION	EACH	219	219	-	-
* 20101200	TREE ROOT PRUNING	EACH	219	219	-	-
20200100	EARTH EXCAVATION	CU YD	8,860	8,860	-	-
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	5,535	5,535	-	-
20800150	TRENCH BACKFILL	CU YD	3,649	3,649	-	-
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	7,852	7,852	-	-
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	45,257	45,257	-	-
* 25000210	SEEDING, CLASS 2A	ACRE	7.00	7.00	-	-
* 25000310	SEEDING, CLASS 4	ACRE	0.25	0.25	-	-
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	755	755	-	-
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	755	755	-	-
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	755	755	-	-
* 25100115	MULCH, METHOD 2	ACRE	8	8	-	-
* 25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	32	32	-	-
* 25200110	SODDING, SALT TOLERANT	SQ YD	14,412	14,412	-	-
* 25200200	SUPPLEMENTAL WATERING	UNIT	227	227	-	-
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	938	938	-	-
28000305	TEMPORARY DITCH CHECKS	FOOT	60	60	-	-
28000400	PERIMETER EROSION BARRIER	FOOT	4,100	4,100	-	-
28000500	INLET AND PIPE PROTECTION	EACH	8	8	-	-
28000510	INLET FILTERS	EACH	133	133	-	-
28100107	STONE RIPRAP, CLASS A4	SQ YD	20	20	-	-
28200200	FILTER FABRIC	SQ YD	20	20	-	-
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	17,498	17,498	-	-
35400100	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 6"	SQ YD	855	855	-	-
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	1,065	1,065	-	-
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	56	56	-	-
40600300	AGGREGATE (PRIME COAT)	TON	229	229	-	-
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20	-	-
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3,556	3,556	-	-

* INDICATES SPECIALTY ITEM

SUMMARY OF QUANTITIES				STU Funding 70% Federal, 30% Local		
				CONSTRUCTION TYPE CODE		
				0004	0021	0040
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	TRAFFIC SIGNALS & LIGHTING	BRIDGE & RETAINING WALL
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	-	-
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	241	241	-	-
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	26	26	-	-
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2,867	2,867	-	-
40701841	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8"	SQ YD	15,571	15,571	-	-
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	1,040	1,040	-	-
42001300	PROTECTIVE COAT	SQ YD	20,151	20,151	-	-
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	2,478	2,478	-	-
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	636	636	-	-
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	91,450	91,450	-	-
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	4,488	4,488	-	-
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	1,100	1,100	-	-
42400800	DETECTABLE WARNINGS	SQ FT	712	712	-	-
44000100	PAVEMENT REMOVAL	SQ YD	17,664	17,664	-	-
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	31,229	31,229	-	-
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	583	583	-	-
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2,747	2,747	-	-
44000300	CURB REMOVAL	FOOT	1,090	1,090	-	-
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	19,911	19,911	-	-
44000600	SIDEWALK REMOVAL	SQ FT	97,250	97,250	-	-
44003100	MEDIAN REMOVAL	SQ FT	1,550	1,550	-	-
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	150	150	-	-
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	528	528	-	-
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	810	810	-	-
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	3,972	3,972	-	-
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	15,600	15,600	-	-
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	2	-	-	2
50102400	CONCRETE REMOVAL	CU YD	2	2	-	-
50105220	PIPE CULVERT REMOVAL	FOOT	105	105	-	-
50200100	STRUCTURE EXCAVATION	CU YD	11	11	-	-
50300225	CONCRETE STRUCTURES	CU YD	16	16	-	-
50800105	REINFORCEMENT BARS	POUND	3,005	3,005	-	-

* INDICATES SPECIALTY ITEM

COPYRIGHT © 2011 BY BAXTER & WOODMAN, INC. \\s0101\proj\06-00090-00-PP-300.sht
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. - 06-00090-00-PP-300.sht
 02/27/2011 10:55:31 AM



DESIGNED - TAO	REVISED -
DRAWN - MAC	REVISED -
CHECKED - TAO	REVISED -
DATE - 10/31/11	FILE - 060670-PH2-S00.sht

**STATE OF ILLINOIS
ORCHARD DRIVE IMPROVEMENTS**

SUMMARY OF QUANTITIES

SCALE: NONE

STA. TO STA.

F.A.U. RTE. 2836	SECTION 06-00090-00-FP	COUNTY COOK	TOTAL SHEETS 200	SHEET NO. 4
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 63635 W-8003661	