

SUMMARY OF QUANTITIES				STU Funding 70% Federal, 30% Local		
				CONSTRUCTION TYPE CODE		
				0004	0021	0040
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	TRAFFIC SIGNALS & LIGHTING	BRIDGE & RETAINING WALL
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	177	177	-	-
Z0062456	TEMPORARY PAVEMENT	SQ YD	173	173	-	-
* Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	5	-	5	-
\$ Z0076600	TRAINEES	HOUR	1,000	1,000	-	-
* A2002916	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2" CALIPER, BALLED AND BURLAPPED	EACH	10	10	-	-
* A2004568	TREE, GINKGO BILOBA MAGYAR ARISTOCRAT (MAGYAR ARISTOCRAT GINKO), TREE FORM, 3" CALIPER BALLED AND BURLAPPED	EACH	10	10	-	-
* A2005316	TREE, LIQUIDAMBAR STYRACIFLUA (AMERICAN SWEETGUM), 2" CALIPER, BALLED AND BURLAPPED	EACH	10	10	-	-
* A2007816	TREE, TILIA AMERICANA (AMERICAN LINDEN/ BASSWOOD), 2" CALIPER, BALLED AND BURLAPPED	EACH	10	10	-	-
* A2008453	TREE, ULMUS ACCOLADE (HYBRID ELM), 3" CALIPER, BALLED AND BURLAPPED	EACH	9	9	-	-
* B2006316	TREE, SYRINGA RETICULATA IVORY SILK (IVORY SILK JAPANESE TREE LILAC), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	9	9	-	-
* X0324450	SEGMENTAL CONCRETE BLOCK WALL, SPECIAL	SQ FT	1,599	-	-	1,599
X0325279	CLASS SI CONCRETE (MISCELLANEOUS)	CU YD	14	-	-	14
X0327037	SPECIAL GRATE NO. 1	EACH	1	1	-	-
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	200	200	-	-
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	65	65	-	-
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	10	10	-	-
X4023000	TEMPORARY ACCESS (ROAD)	EACH	13	13	-	-
X5537600	STORM SEWERS TO BE CLEANED 8"	FOOT	500	500	-	-
X5537700	STORM SEWERS TO BE CLEANED 10"	FOOT	983	983	-	-
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	1,039	1,039	-	-
X5537900	STORM SEWERS TO BE CLEANED 15"	FOOT	1,255	1,255	-	-
X5538000	STORM SEWERS TO BE CLEANED 18"	FOOT	1,673	1,673	-	-
X5538200	STORM SEWERS TO BE CLEANED 24"	FOOT	770	770	-	-
X5538400	STORM SEWERS TO BE CLEANED 30"	FOOT	240	240	-	-
X5538500	STORM SEWERS TO BE CLEANED 33"	FOOT	60	60	-	-
X5538600	STORM SEWERS TO BE CLEANED 36"	FOOT	1,175	1,175	-	-
X5538700	STORM SEWERS TO BE CLEANED 42"	FOOT	270	270	-	-
X5538800	STORM SEWERS TO BE CLEANED 48"	FOOT	1,305	1,305	-	-
X5539000	STORM SEWERS TO BE CLEANED 60"	FOOT	20	20	-	-
X6020099	MANHOLES, TYPE A, 9'-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	2	2	-	-

\* INDICATES SPECIALTY ITEM

\$ CONSTRUCTION TYPE CODE 0042

SUMMARY OF QUANTITIES				STU Funding 70% Federal, 30% Local		
				CONSTRUCTION TYPE CODE		
				0004	0021	0040
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	TRAFFIC SIGNALS & LIGHTING	BRIDGE & RETAINING WALL
X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	21	21	-	-
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	14	14	-	-
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	-	-
* X8570226	FULL-ACTUATED CONTROLLER AND CABINET, TYPE IV, SPECIAL	EACH	1	-	1	-
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	1,924	-	1,924	-
* X8760200	ACCESSIBLE PEDESTRIAN SIGNALS	EACH	16	-	16	-
* X8760250	VIBROTACTILE FEATURE	EACH	8	-	8	-
XX000717	STORM SEWER CONNECTION, SPECIAL	EACH	1	1	-	-
X5539066	STORM SEWERS TO BE CLEANED 66"	FOOT	100	100	-	-
* Xx008b12	LIGHT POLE, FIBERGLASS 35 FT. M.H., 12 FT. ARM, TENON MOUNT	EACH	29	-	29	-
X4420682	CLASS B PATCHES, TYPE II, 10 INCH (SPECIAL)	SQ YD	86	86	-	-
X4420683	CLASS B PATCHES, TYPE III, 10 INCH (SPECIAL)	SQ YD	17	17	-	-
X4420684	CLASS B PATCHES, TYPE IV, 10 INCH (SPECIAL)	SQ YD	70	70	-	-

\* INDICATES SPECIALTY ITEM

COPYRIGHT © 2011 BY BAXTER & WOODMAN, INC.  
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM  
 LICENSE NO. 06-00090-00-FP - EXPIRES 12/31/2013  
 10/27/2011 10:40:11 AM



DESIGNED - TAO	REVISED -
DRAWN - MAC	REVISED -
CHECKED - TAO	REVISED -
DATE - 10/31/11	FILE - 060670-PH2-S00.shp

**STATE OF ILLINOIS  
ORCHARD DRIVE IMPROVEMENTS**

**SUMMARY OF QUANTITIES**

SCALE: \_\_\_\_\_ STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2836	06-00090-00-FP	COOK	200	8
FED. ROAD DIST. NO. 1   ILLINOIS   FED. AID PROJECT			CONTRACT NO. 63635	
			M-8003661	