

EARTHWORK

EARTHWORK							
LOCATION STA TO STA	UNDERCUT AND PGE REPLACEMENT (CU YD)	UNSUITABLE EXCAVATION (TOPSOIL) (CU YD)	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	EARTH EXCAVATION (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
ORCHARD DRIVE							
STA 100+35 TO STA 116+68 (SIDEWALK)	-	56	56	190	162	-	162
STA 116+68 TO STA 118+56 (INDIANWOOD BLVD)	16	20	36	101	86	15	71
STA 118+56 TO STA 123+48 (SIDEWALK)	-	15	15	25	22	-	22
STA 123+48 TO STA 125+66 (MAIN STREET)	16	25	41	110	94	20	74
STA 118+56 TO STA 123+48 (SIDEWALK)	-	25	25	45	39	-	39
STA 132+08 TO STA 145+80 (RESURFACING)	62	565	627	482	410	267	143
STA 145+80 TO STA 159+30 (RECONSTRUCTION)	1,507	523	2,030	2,923	2,485	447	2,038
STA 159+30 TO STA 181+97 (RESURFACING)	99	617	716	839	714	446	268
STA 181+97 TO STA 197+26 (RECONSTRUCTION)	752	374	1,126	3,357	2,854	276	2,578
STA 197+26 TO STA 217+60 (RESURFACING)	89	773	862	788	670	251	419
TOTAL	2,540	2,995	5,535	8,860	7,535	1,720	5,815

COPYRIGHT © 2011 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 NO. - 06-00090-00-FP
 DATE - 10/24/11
 PROJECT - 060670-PH2-SCHEDULE.DWG
 FILE - 060670-PH2-SCHEDULE.DWG



DESIGNED - REW	REVISED -
DRAWN - MAC	REVISED -
CHECKED - TAO	REVISED -
DATE - 10/24/11	FILE - 060670-PH2-SCHEDULE.shx

**STATE OF ILLINOIS
ORCHARD DRIVE IMPROVEMENTS**

SCHEDULE OF QUANTITIES

SCALE: NONE

STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2836	06-00090-00-FP	COOK	200	16
CONTRACT NO. 63635				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-8003(661)				