

STORM SEWER SCHEDULE										
LOCATION	STORM SEWER REMOVAL 15"	STORM SEWER REMOVAL 18"	TOP RIM ELEVATION	INVERT ELEVATION	MANHOLES, TYPE A 4'-DIAMETER, TYPE 1 FRAME CLOSED LID	MANHOLES, TYPE A 6'-DIAMETER, TYPE 1 FRAME CLOSED LID	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	STORM SEWER (WATER MAIN REQUIREMENTS) 30 INCH	TRENCH BACKFILL
	55100700	55100900			60218400	60223800	Z0056610	Z0056612	Z0056620	20800150
	FOOT	FOOT			EACH	EACH	FOOT	FOOT	FOOT	CU YD
FAU 2556 (WALNUT LANE)										
LT STA 124+00 TO LT STA 124+13		13								
LT STA 124+00 TO LT STA 124+08				786.80(18° S)-786.70 (18° S)			8			2.2
25.5' LT STA 124+11			791.99 +/-	786.70(18° S), 784.95 (30° NW)	1					
LT STA 124+11 TO LT STA 124+13				784.95 (30° NW)-784.90 30° NW				7		4.9
LT STA 124+41 TO LT STA 124+50	9									
25.5 LT STA 124+46			792.12 +/-	786.00 (15° N) -785.70 (15° W)	1					
LT STA 124+45 TO LT STA 124+46				785.70 (15° W) - 785.65 (15° W)			9			3.2
LT STA 124+48 TO LT STA 124+50				786.00 (15° N) - 786.17 (15° N)			2			0.7
TOTAL	9	13			1	1	11	8	7	11.0

31101910 SUBBASE GRANULAR MATERIAL, TYPE B 12"	
LOCATION	SQ YD
FAU 2556 (WALNUT LANE)	
CL. STA 123+90 TO CL. STA 124+56	422
TOTAL	422

DETECTABLE WARNINGS, SPECIAL	
LOCATION	SQ FT
FAU 2556 (WALNUT LANE)	
LT. STA 124+54 TO LT. STA 124+56	8
TOTAL	8

54213891 STEEL END SECTIONS 36"	
LOCATION	EACH
FAU 2556 (WALNUT LANE)	
52' LT. STA 124+03	1
TOTAL	1

WATERMAIN SCHEDULE				
LOCATION	AUXILIARY VALVE AND VALVE BOX	WATER MAIN 8"	STEEL CASINGS 14"	TRENCH BACKFILL
	EACH	FOOT	FOOT	20800150 CU YD
LT STA 123+95	1			
LT STA 123+95 TO LT STA 124+49		56		46.2
LT STA 124+12 TO LT STA 124+48			36	
LT STA 124+49	1			
TOTAL	2	56	36	46.2

50300300 PROTECTIVE COAT	
LOCATION	SQ YD
FAU 2556 (WALNUT LANE)	
LT. STA 123+90 TO LT. STA 124+56 (SIDEWALK)	50
LT. STA 123+90 TO LT. STA 124+56 (CCC&G)	17
RT. STA 123+90 TO RT. STA 124+56 (SIDEWALK)	41
RT. STA 123+90 TO RT. STA 124+56 (CCC&G)	17
TOTAL	125

CHAIN LINK FENCE SCHEDULE		
LOCATION	CHAIN LINK FENCE, 4'	CHAIN LINK FENCE REMOVAL
	66400105	X6640300
	FOOT	FOOT
LT. STA 123+85 TO LT. ST 123+99	14	
LT. STA 124+44 TO LT. ST 124+45	12	
LT. STA 124+44 TO LT. ST 124+56		12
TOTAL	26	12