

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY LAPP 0005
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	262	262
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	105	105
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2	2
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2	2
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2	2
25200110	SODDING, SALT TOLERANT	SQ YD	105	105
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	4	4
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	2	2
35800100	PREPARATION OF BASE	SQ YD	18,891	18,891
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	50	50
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,849	3,849
40600300	AGGREGATE (PRIME COAT)	TON	77	77
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	9	9
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2,694	2694
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	351	351
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	264	264
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	0.3	0.3
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2,156	2,156
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1.6	1.6

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY LAPP 0005
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	780	780
42400800	DETECTABLE WARNINGS	SQ FT	70	70
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	2	2
44000167	HOT-MIX ASPHALT SURFACE REMOVAL, 4 1/2"	SQ YD	18,891	18,891
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1.6	1.6
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	290	290
44000600	SIDEWALK REMOVAL	SQ FT	780	780
44002210	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/2"	SQ YD	2,001	2,001
44201773	CLASS D PATCHES, TYPE I, 11 INCH	SQ YD	472	472
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	472	472
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	472	472
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	472	472
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	102	102
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	188	188
67100100	MOBILIZATION	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2,100 (1)	2,100 (1)

\* = SPECIALTY ITEM

(1) = INCLUDES REMOVAL

FILE NAME = \$FILES



USER NAME = #USER#	DESIGNED - EVI	REVISED -
DRAWN - KJB	REVISED -	
CHECKED - DAK	REVISED -	
PLOT DATE = #DATE#	DATE - 5/11/2011	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

NTS SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1485	11-00150-00-RS	DUPAGE	21	3
CONTRACT NO. 63641				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				