

SUMMARY OF QUANTITIES

SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
					80% FEDERAL 20% STATE		NON-PARTICIPATING 100% LOCAL	
					ROADWAY 0004 URBAN	BRIDGE 0011 URBAN	TRAINEES 0042 URBAN	
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	159	159			
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	152	152			
	20101000	TEMPORARY FENCE	FOOT	383	383			
	20101100	TREE TRUNK PROTECTION	EACH	17	17			
	20200100	EARTH EXCAVATION	CU YD	1,210	1210			
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	655	655			
	20300100	CHANNEL EXCAVATION	CU YD	255	255			
	20400800	FURNISHED EXCAVATION	CU YD	50	50			
	20800150	TRENCH BACKFILL	CU YD	55	55			
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	660	660			
*	21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	3,670	3670			
	21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	100	100			
*	25000100	SEEDING, CLASS 1	ACRE	0.25	0.25			
*	25000210	SEEDING, CLASS 2A	ACRE	0.75	0.75			
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	69	69			
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	69	69			
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	69	69			
*	25100630	EROSION CONTROL BLANKET	SQ YD	3,338	3338			
*	25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	632	632			
*	25100900	TURF REINFORCEMENT MAT	SQ YD	126	126			
*	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	261	261			
	28000305	TEMPORARY DITCH CHECKS	FOOT	480	480			
	28000400	PERIMETER EROSION BARRIER	FOOT	1,833	1833			
	28000500	INLET AND PIPE PROTECTION	EACH	3	3			
	28000510	INLET FILTERS	EACH	1	1			
	28100105	STONE RIPRAP, CLASS A3	SQ YD	4	4			
	28100107	STONE RIPRAP, CLASS A4	SQ YD	360	30	330		
	28200200	FILTER FABRIC	SQ YD	360	30	330		
	31101100	SUBBASE GRANULAR MATERIAL, TYPE B	CU YD	36	36			
	35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	201	201			
	35501312	HOT-MIX ASPHALT BASE COURSE, 7"	SQ YD	1,751	1751			
	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6	5			1

FILE NAME = W:\Projects\2010\000025_Burr-Farson\I\Wood\Civil\Ugpr\ShA\S001.dgn