

SUMMARY OF QUANTITIES

SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
					80% FEDERAL 20% STATE			NON-PARTICIPATING 100% LOCAL
					ROADWAY 0004 URBAN	BRIDGE 0011 URBAN	TRAINEES 0042 URBAN	
	40600300	AGGREGATE (PRIME COAT)	TON	12	3			9
	40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	82				82
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	202				202
	40600990	TEMPORARY RAMP	SQ YD	25				25
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	552	219			333
	42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	54	54			
	44000100	PAVEMENT REMOVAL	SQ YD	1,945	1909			36
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	345				345
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	338	305			33
	44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	15				15
	44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	22				22
	48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	301	249			52
	48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	29				29
	48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	567	567			
	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1		
	50105220	PIPE CULVERT REMOVAL	FOOT	143				143
	50200100	STRUCTURE EXCAVATION	CU YD	196		196		
	50300225	CONCRETE STRUCTURES	CU YD	47.7		47.7		
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	164.8		164.8		
	50300260	BRIDGE DECK GROOVING	SQ YD	419		419		
	50300280	CONCRETE ENCASEMENT	CU YD	3.6		3.6		
	50300300	PROTECTIVE COAT	SQ YD	439		439		
	50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1		
	50500505	STUD SHEAR CONNECTORS	EACH	1,020		1020		
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	45,150		45150		
	50800515	BAR SPLICERS	EACH	66		66		
	50901050	STEEL RAILING, TYPE SM	FOOT	176		176		
	51201600	FURNISHING STEEL PILES HP12X53	FOOT	190		190		
	51500100	NAME PLATES	EACH	1		1		
	52100520	ANCHOR BOLTS, 1"	EACH	20		20		
	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1			
	54215418	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 18"	EACH	1	1			

FILE NAME: M:\Projects\2011\080925_Burr-Ferguson\Road\Civil\Drawings\54002.dgn

WBK WILLS BURKE KELSEY ASSOCIATES LTD.
116 West Main Street, Suite 201
St. Charles, Illinois 60174
(630) 443-7755

USER NAME = #USER#	DESIGNED - KMA	REVISED -
	DRAWN - NDP	REVISED -
PLOT SCALE =	CHECKED - SBP	REVISED -
PLOT DATE = 11/17/2011	DATE - 10/24/11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 4 OF 76 SHEETS STA. TO STA.

T.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
194	08-14117-00-BR	KANE	76	4
CONTRACT NO. 63645				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				