

# SCHEDULE OF QUANTITIES

**20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)**

UNIT	LOCATION	O/S (LT)	O/S (RT)	COMMENTS
10	10+60.50	20.6		10"
12	11+15.50		36.3	6", 6"
9	11+19.50		33.5	9"
7	11+20.30		31.3	8"
8	11+56.10		33.2	8"
17	11+56.90		32.8	8", 9"
7	12+03.42		24.7	7"
6	11+82.30	33.9		6"
6	11+96.80	34.1		6"
6	12+12.40	34.6		6"
6	12+30.30	35.0		6"
10	12+36.30		36.6	10"
7	13+03.80		29.3	7"
10	13+30.06	35.3		10"
7	13+44.50		30.2	7"
8	13+47.90		29.1	8"
9	13+68.70		36	9"
14	14+40.30		29.9	14"

**159 TOTAL**

**20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)**

UNIT	LOCATION	O/S (LT)	O/S (RT)	COMMENTS
29.0	8+05.60		21.3	29"
30	10+17.30	28.4	30.0	30"
36	10+56.70	36.9		36"
20	11+49.50		36.4	20
16	13+59.50		31.8	16
21	13+98.30		26.9	21

**152 TOTAL**

**20101100 TREE TRUNK PROTECTION**

EACH	LOCATION	O/S (LT.)	REMARKS
1	8+69.70	38.3	LT
1	10+90.00	37.9	RT
1	11+42.00	60.6	LT
1	11+45.00	55.1	LT
1	11+49.50	36.7	RT
1	11+84.00	45.1	LT
1	12+36.30	36.6	RT
1	13+03.80	29.3	RT
1	13+30.60	35.3	LT
1	13+40.30	38.8	LT
1	13+44.50	30.2	RT
1	13+47.90	29.1	RT
1	13+59.50	31.8	RT
1	13+68.70	36.0	RT
1	13+98.30	26.9	RT
1	14+40.30	29.9	RT
1	15+68.10	31.4	RT

**17 TOTAL**

**20800150 TRENCH BACKFILL**

VOLUME (CU YD)	LOCATION	O/S	LENGTH (FT)	WIDTH (FT)	DEPTH (FT)	REMARKS
8.8	7+67.70	RT	58	2.8	1.5	15" CMP REMOVED
6.3	7+67.70	RT	41	2.8	1.5	15" CMP RELOCATED
39.0	9+62.00	LT	58.5	3.0	6.0	18" STORM
<b>55.0</b>	<b>TOTAL</b>					

**50105220 PIPE CULVERT REMOVAL**

FOOT	LOCATION	O/S	REMARKS
70	7+31.76	8+00.14	RT CREEKSIDE DR. INTERSECTION
73	9+27.49	9+99.90	LT DRIVEWAY
<b>143</b>	<b>TOTAL</b>		

**54213657 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"**

EACH	LOCATION	O/S	REMARKS
1	11+15.38	27.1	RT
<b>1</b>	<b>TOTAL</b>		

**54215418 CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 18"**

EACH	LOCATION	O/S	REMARKS
1	11+14.00	25.0	LT
<b>1</b>	<b>TOTAL</b>		

FILE NAME = W:\P\Projects\2010\100225 Burr-Ferron\1\Drawings\Sched\Schedule.dgn



USER NAME = #USER#	DESIGNED - KMA	REVISED -
PLOT SCALE =	DRAWN - NDP	REVISED -
PLOT DATE = 11/17/2011	CHECKED - SBP	REVISED -
	DATE - 10/24/11	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES	
SCALE:	SHEET NO. 7 OF 76 SHEETS STA. TO STA.

T.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
194	08-14117-00-BR	KANE	76	7
CONTRACT NO. 63645				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				