

SCHEDULE OF QUANTITIES

54215550 METAL END SECTIONS 15"

EACH	LOCATION	O/S		REMARKS
1	7+31.01	32.0	RT	SOUTH SIDE OF CREEK SIDE DR.
1	8+00.99	32.0	RT	NORTH SIDE OF CREEK SIDE DR.
2	TOTAL			

54247090 GRATING FOR CONCRETE FLARED END SECTION 12"

EACH	LOCATION	O/S		REMARKS
1	11+15.38	27.1	RT	
1	TOTAL			

542C0220 PIPE CULVERTS, CLASS C, TYPE 1 15"

FOOT	LOCATION	O/S		REMARKS
68	7+32.00	8+00.00	RT	
68	TOTAL			

550A0050 STORM SEWERS, CLASS A, TYPE 1 12"

FOOT	LOCATION	O/S		REMARKS
10	11+04.32	11+14.38	RT	
10	TOTAL			

550A0090 STORM SEWERS, CLASS A, TYPE 1 18"

FOOT	LOCATION	O/S		REMARKS
150	9+00.00	10+50.00	LT	
64	10+50.00	11+06.61	LT	
214	TOTAL			

60100060 CONCRETE HEADWALLS FOR PIPE DRAINS

EACH	LOCATION	O/S		REMARKS
1	13+63.00	23.0	RT	
1	TOTAL			

60107600 PIPE UNDERDRAINS 4"

FOOT	LOCATION	O/S		REMARKS
38	9+00.00		LT/RT	ACROSS PVMT
43	11+04.49		LT/RT	ACROSS PVMT
48	11+66.51		LT/RT	ACROSS PVMT
13	13+56.06	13+68.89	RT	ALONG EOP
27	13+56.28		LT/RT	ACROSS PVMT
8	13+68.89		RT	
177	TOTAL			

60200805 CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE

EACH	LOCATION	O/S		REMARKS
1	9+00.00	23.0	LT	
1	TOTAL			

60218300 MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID

EACH	LOCATION	O/S		REMARKS
1	10+50.00	23.0	LT	
1	TOTAL			

60235300 INLETS, TYPE A, TYPE 1 FRAME, CLOSED LID

EACH	LOCATION	O/S		REMARKS
1	11+04.32	27.0	RT	
1	TOTAL			

60500050 REMOVING CATCH BASINS

EACH	LOCATION	O/S		REMARKS
1	9+27.49	22.6	LT	BY DRIVEWAY
1	TOTAL			

72000100 SIGN PANEL - TYPE 1

SQ FT	LOCATION	O/S (LT)	O/S (RT)	COMMENTS
6.25	7+87.30		30.5	STOP SIGN, R1-1 30"x30"
7.00	TOTAL (Rounded up to next integer)			

FILE NAME = W:\Projects\2010\100025 Burr-Ferson\11\Road\Civil\Sign\Sht\SGSCHEDULE.dgn



USER NAME = #USER#	DESIGNED - KMA	REVISED -
PLOT SCALE =	DRAWN - NDP	REVISED -
PLOT DATE = 11/17/2011	CHECKED - SBP	REVISED -
	DATE - 10/24/11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 8 OF 76 SHEETS STA. TO STA.

T.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
194	08-14117-00-BR	KANE	76	8
CONTRACT NO. 63645			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	