

# SCHEDULE OF QUANTITIES

72400500 RELOCATE SIGN PANEL ASSEMBLY - TYPE A

UNIT	LOCATION	O/S (LT)	O/S (RT)	COMMENTS
1	10+75.30		19.2	KANE CO. STREAMS SIGN
1	11+95.10	20.5		KANE CO. STREAMS SIGN
<b>2</b>	<b>TOTAL</b>			

Z0025500 FURNISHING AND INSTALLING PROPERTY MARKERS

UNIT	LOCATION	O/S (LT)	O/S (RT)	COMMENTS
1	9+36.76	35.48	LT	
1	13+42.80	33.91	LT	
1	13+41.01	40.87	LT	
<b>3</b>	<b>TOTAL</b>			

## EROSION CONTROL SCHEDULE

LOCATION	25100630	25100635	25100900	28000250	28000305	28000400	28000500	28000510	28100105	28100107	28200200	XX006345
	EROSION CONTROL BLANKET	HEAVY DUTY EROSION CONTROL BLANKET	TURF REINFORCEMENT MAT	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	INLET FILTERS	STONE RIPRAP, CLASS A3	STONE RIPRAP, CLASS A4	FILTER FABRIC	TURBIDITY BARRIER
	(SQ YD)	(SQ YD)	(SQ YD)	(POUND)	(FOOT)	(FOOT)	(EACH)	(EACH)	(SQ YD)	(SQ YD)	(SQ YD)	(FOOT)
<b>MAINLINE</b>												
7+00.00 - 8+00.00	266.3			16.5	10	139	1					
8+00.00 - 8+50.00	198.1			12.3	30	104			1.7			
8+50.00 - 9+00.00	211.9			13.1	40	111	1	1				
9+00.00 - 9+50.00	227.0			14.1	40	122						
9+50.00 - 10+00.00	211.3			13.1	40	89						
10+00.00 - 10+50.00	219.7			13.6	80	114						
10+50.00 - 11+06.50	119.0	151.0	125.6	26.1		126						
<b>BRIDGE</b>	51.5	84.0		13.6	10	81				360	360	197
11+64.50 - 12+00.00	105.6	67.8		15.0	20	75						
12+00.00 - 12+50.00	135.2	82.2		18.6	10	100						
12+50.00 - 13+00.00	129.3	75.8		17.4	30	100						
13+00.00 - 13+50.00	123.4	67.3		16.0	10	100						
13+50.00 - 14+00.00	208.4	3.2		13.3	10	105						
14+00.00 - 14+50.00	252.7			15.7	20	100						
14+50.00 - 15+00.00	255.6			15.8	20	100						
15+00.00 - 15+50.00	255.6			15.8	10	100						
15+50.00 - 15+70.00	108.1			6.7		40						
15+70.00 - 16+70.00	58.7			3.6		25			1.7			
<b>MAINTENANCE</b>	200	100			100	100.00	1					
<b>TOTAL</b>	<b>3,338</b>	<b>632</b>	<b>126</b>	<b>261</b>	<b>480</b>	<b>1,833</b>	<b>3</b>	<b>1</b>	<b>4</b>	<b>360</b>	<b>360</b>	<b>197</b>

FILE NAME = m:\projects\2010\100225 burr\resources\100225\1\1\dgn\skt\SCHEDULE3.dgn



USER NAME = #USER#	DESIGNED - KMA	REVISED -
PLOT SCALE =	DRAWN - NDP	REVISED -
PLOT DATE = 10/19/2011	CHECKED - SBP	REVISED -
	DATE - 10/24/11	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 9 OF 76 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
194	08-14117-00-BR	KANE	76	9
CONTRACT NO. 63645				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				