

# LANDSCAPING SCHEDULE

LANDSCAPING ITEMS	21101625	25000100	25000210	25000400	25000500	25000600	X2501800	X2501820
LOCATION	TOPSOIL FURNISH AND PLACE, 6"	SEEDING, CLASS 1	SEEDING, CLASS 2A	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	SEEDING, CLASS 4 (MOD)	SEEDING, CLASS 5 (MOD)
	(SQ YD)	(ACRE)	(ACRE)	(POUND)	(POUND)	(POUND)	(ACRE)	(ACRE)
<b>MAINLINE</b>								
7+00.00 - 8+00.00	266.3		0.055	5.0	5.0	5.0		
8+00.00 - 8+50.00	198.1	0.009	0.041	3.7	3.7	3.7		
8+50.00 - 9+00.00	211.9	0.018	0.035	3.9	3.9	3.9		
9+00.00 - 9+50.00	227.0	0.026	0.029	4.2	4.2	4.2		
9+50.00 - 10+00.00	211.3	0.014	0.018	3.9	3.9	3.9		
10+00.00 - 10+50.00	219.7	0.014	0.031	4.1	4.1	4.1		
10+50.00 - 11+06.50	270.0	0.011	0.010	5.0	5.0	5.0	0.018	0.018
<b>BRIDGE</b>								
11+64.50 - 12+00.00	135.5	0.013		2.5	2.5	2.5	0.011	0.011
11+64.50 - 12+00.00	173.5	0.010	0.009	3.2	3.2	3.2	0.014	0.014
12+00.00 - 12+50.00	217.5	0.009	0.018	4.0	4.0	4.0	0.017	0.017
12+50.00 - 13+00.00	205.1	0.006	0.018	3.8	3.8	3.8	0.016	0.016
13+00.00 - 13+50.00	190.7		0.019	3.5	3.5	3.5	0.014	0.014
13+50.00 - 14+00.00	211.5		0.043	3.9	3.9	3.9	0.001	0.001
14+00.00 - 14+50.00	252.7		0.052	4.7	4.7	4.7		
14+50.00 - 15+00.00	255.6		0.053	4.8	4.8	4.8		
15+00.00 - 15+50.00	255.6		0.053	4.8	4.8	4.8		
15+50.00 - 15+70.00	108.1		0.022	2.0	2.0	2.0		
15+70.00 - 16+70.00	58.7		0.012	1.1	1.1	1.1		
<b>TOTAL</b>	<b>3,670</b>	<b>0.25</b>	<b>0.75</b>	<b>69</b>	<b>69</b>	<b>69</b>	<b>0.10</b>	<b>0.10</b>

LANDSCAPING ITEMS	A2000616	A2002316	A2002716	A2005116	A2006416	A2006516	A2007816	A2008466	C2001636	C2012436	D2001788	D2002288
LOCATION	TREE, ACER PLATANOIDES (NORWAY MAPLE), 2" CALIPER	TREE, BETULA NIGRA (RIVER BIRCH), 2" CALIPER	TREE, CARYA OVATA (SHAGBARK HICKORY), 2" CALIPER	TREE, JUGLANS NIGRA (BLACK WALNUT), 2" CALIPER	TREE, QUERCUS ALBA (WHITE OAK), 2" CALIPER	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER	TREE, TILIA AMERICANA (AMERICAN LINDEN/ BASSWOOD), 2" CALIPER	TREE, ULMUS AMERICANA (AMERICAN ELM), 2" CALIPER	SHRUB, CORNUS SERICEA (REDSIER DOGWOOD), 3'	SHRUB, VIBURNUM LENTAGO (NANNYBERRY VIBURNUM), 3'	EVERGREEN, PICEA ABIES (NORWAY SPRUCE), 8'	EVERGREEN, PICEA PUNGENS GLAUCA (COLORADO BLUE SPRUCE), 8'
	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)
<b>MAINLINE</b>												
7+00.00 - 8+00.00												
8+00.00 - 8+50.00												
8+50.00 - 9+00.00												
9+00.00 - 9+50.00												
9+50.00 - 10+00.00												
10+00.00 - 10+50.00												
10+50.00 - 11+06.50				2	1						2.0	1
<b>BRIDGE</b>												
11+64.50 - 12+00.00						1						
12+00.00 - 12+50.00						1			4.0	3		
12+50.00 - 13+00.00		2								2		
13+00.00 - 13+50.00												
13+50.00 - 14+00.00							1					
14+00.00 - 14+50.00	2						2					
14+50.00 - 15+00.00				2								
15+00.00 - 15+50.00				2	1							
15+50.00 - 15+70.00	1			2								
15+70.00 - 16+70.00			1	1								
<b>TOTAL</b>	<b>3</b>	<b>2</b>	<b>2</b>	<b>8</b>	<b>2</b>	<b>2</b>	<b>3</b>	<b>3</b>	<b>4</b>	<b>5</b>	<b>2</b>	<b>2</b>

FILE NAME = K:\Projects\2010\100025 BurrFertson\1\Drawn\Sh1\Schedule7.dgn

<b>WILLS BURKE KELSEY ASSOCIATES LTD.</b> <small>116 West Main Street, Suite 201 St. Charles, Illinois 60174 (630) 443-7755</small>	USER NAME = #USER#	DESIGNED - KMA	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>				F.A.P. RTE. 194	SECTION 08-14117-00-BR	COUNTY KANE	TOTAL SHEETS 76	SHEET NO. 13
	PLOT SCALE =	CHECKED - SBP	REVISED -		SCALE:	SHEET NO. 13 OF 76 SHEETS	STA.	TO STA.	CONTRACT NO. 63645				
	PLOT DATE = 11/21/2011	DATE - 10/24/11	REVISED -		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT								