



LEGEND

Concrete Removal

BILL OF MATERIAL

Item	Unit	Quantity
Temporary Sheet Piling	Sq. Ft.	1,474

Notes:

1. The stream work is expected in the low water level. The cost of dewatering the area behind the temporary sheet piling for existing structure removal is included in the pay item Temporary Sheet Piling.
2. Adjust elevation based on water level in construction.
3. If the bottom of Concrete removal is below the top of the existing footing, remove the entire existing footing.
4. If the Contractor chooses to alter the temporary cantilevered sheet piling design requirements shown the plans, a design submittal including plan details and calculations will be required for review and acceptance by the Engineer.

FILE NAME = W:\Projects\2010\100025 BurrFerson\I\Need\Structural\Draw\0453080-003-SheetP_Ling.dgn

WILLS BURKE KELSEY ASSOCIATES LTD.
 116 West Main Street, Suite 201
 St. Charles, Illinois 60174

USER NAME = nporris
 PLOT SCALE =
 PLOT DATE = 10/18/2011

DESIGNED - HLF
 CHECKED - AEU
 DRAWN - HLF
 CHECKED - AEU

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**TEMPORARY SHEET PILING DETAILS
 STRUCTURE NO. 045-3080**

SHEET NO. 3 OF 20 SHEETS

T.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0194	08-14117-00-BR	KANE	76	36
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
CONTRACT NO. 63645				