

SUMMARY OF QUANTITIES

ITEM NO.	ITEM DESCRIPTION	UNIT	0005 QUANTITY
20200100	Earth Excavation	CU YD	550
20400800	Furnished Excavation	CU YD	90
20800150	Trench Backfill	CU YD	175
21101615	Topsoil Furnish and Place, 4"	SQ YD	9,000
25000110	Seeding, Class 1A	ACRE	1.86
25000400	Nitrogen Fertilizer Nutrient	POUND	40
25000500	Phosphorus Fertilizer Nutrient	POUND	40
25000600	Potassium Fertilizer Nutrient	POUND	40
25100630	Erosion Control Blanket	SQ YD	9,000
28000400	Perimeter Erosion Barrier	FOOT	1,300
28000500	Inlet and Pipe Protection	EACH	45
28100127	Stone Riprap, Class B4	SQ YD	100
28200200	Filter Fabric	SQ YD	100
31101200	Sub-Base Granular Material, Type B 4"	SQ YD	3,000
35600700	Hot-Mix Asphalt Base Course Widening, 6"	SQ YD	3,000
40600100	Bituminous Materials (Prime Coat)	GAL	700
40600300	Aggregate (Prime Coat)	TON	100
40600982	Hot-Mix Asphalt Surface Removal - Butt Joint	SQ YD	1,000
40603080	Hot-Mix Asphalt Binder Course, IL-19.0, N50	TON	1,500
40603335	Hot-Mix Asphalt Surface Course, Mix 'D', N50	TON	1,800
42400200	Portland Cement Concrete Sidewalk 5 Inch	SQ FT	60
44000100	Pavement Removal	SQ YD	2,800
44000159	Hot-Mix Asphalt Surface Removal, 2 1/2"	SQ YD	10,500
44000200	Driveway Pavement Removal	SQ YD	370
44000600	Sidewalk Removal	SQ FT	60
44201713	Class D Patches, Type I, 6 Inch	SQ YD	200
44201717	Class D Patches, Type II, 6 Inch	SQ YD	200
44201721	Class D Patches, Type III, 6 Inch	SQ YD	200
44201723	Class D Patches, Type IV, 6 Inch	SQ YD	200
44300100	Area Reflective Crack Control Treatment	SQ YD	10,500
44300200	Strip Reflective Crack Control Treatment	FOOT	8,400

ITEM NO.	ITEM DESCRIPTION	UNIT	0005 QUANTITY
54213660	Precast Reinforced Concrete Flared End Section 15"	EACH	1
54213663	Precast Reinforced Concrete Flared End Section 18"	EACH	1
54213669	Precast Reinforced Concrete Flared End Section 24"	EACH	4
54247130	Grating for Concrete Flared End Section 24"	EACH	2
550A0360	Storm Sewers, Class A, Type 2 15"	FOOT	100
550A0380	Storm Sewers, Class A, Type 2 18"	FOOT	100
550A0410	Storm Sewers, Class A, Type 2 24"	FOOT	200
550B0340	Storm Sewers, Class B, Type 2 12"	FOOT	100
550B0360	Storm Sewers, Class B, Type 2 15"	FOOT	350
55100400	Storm Sewer Removal 10"	FOOT	100
55100500	Storm Sewer Removal 12"	FOOT	500
60207605	Catch Basins, Type C, Type 8 Grate	EACH	7
60236200	Inlets, Type A, Type 8 Grate	EACH	1
60250200	Catch Basins to be Adjusted	EACH	2
60265700	Valve Vaults to be Adjusted	EACH	1
67100100	Mobilization	L SUM	1
70102620	Traffic Control and Protection, Standard 701501	L SUM	1
* 78000200	Thermoplastic Pavement Marking - Line 4"	FOOT	16,500
* 78000650	Thermoplastic Pavement Marking - Line 24"	FOOT	100
* 78100100	Raised Reflective Pavement Marker	EACH	12
78300200	Raised Reflective Pavement Marker Removal	EACH	12
X4811900	Aggregate Shoulders (Special)	TON	150
X6026050	Sanitary Manholes to be Adjusted	EACH	3
XX004774	Brick Driveway Removal and Replacement	SQ FT	500
XX007729	Detectable Warnings, Special	SQ FT	16
Z0004510	Hot-Mix Asphalt Driveway Pavement, 3"	SQ YD	420
Z0018700	Drainage Structures to be Removed	EACH	7
Z0030850	Temporary Information Signing	SQ FT	52
Δ Z0076600	Trainees	HOUR	500

Δ 0042

* SPECIALTY ITEM

FILE NAME = 8101-055 PR4.DWG	USER NAME = GW3	DESIGNED - DJG	REVISED - 10.14.2011	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			FAU RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 1:1	DRAWN - GW3	CHECKED - DJG	REVISED - 10.28.2011					2718	11-00012-00-RS	LAKE	40	3
PLOT DATE = 8/24/2011	DATE - 08.24.2011				SCALE NONE	SHEET NO. 3 OF 40 SHEETS	STA.	TO STA.	CONTRACT #: 63646			
										ILLINOIS FED. AID PROJECT		