



SEE TEMPORARY CAUSEWAY SHEET FOR DETAILS OF CAUSEWAY PLACED IN PREVIOUS CONTRACT.

- LEGEND:**
- ADDENDUM 1-6-12  
CULVERT INLET PROTECTION - STONE, XX006723 & XX006723
  - INLET & PIPE PROTECTION, 28000500
  - TEMPORARY DITCH CHECK, 28000300
  - INLET FILTERS, 28000510
  - PERIMETER EROSION BARRIER, 28000400
  - TEMPORARY FENCE, 20101000
  - TURBIDITY CURTAIN, XX003967
  - PERIMETER EROSION BARRIER, ROLLED EXCELSIOR XX006729
  - SEDIMENT BASIN, 20200300
  - MULCH, METHOD 2, 25100115
  - RIP RAP, 28100105 & 28100107
  - STABILIZED CONSTRUCTION ENTRANCE, X0322671
  - HAUL ROAD

**NOTE**  
 THE TOTAL ACREAGE OF DISTURBED AREA WITHIN THE FOX RIVER SHALL NOT EXCEED 0.25 AC AT ANY ONE TIME.  
 TEMPORARY BRIDGE WILL BE USED TO ACCESS PIER #2 AND PIER #3 SEE SPECIFICATIONS FOR DETAIL  
 SEE FOX RIVER EROSION AND SEDIMENT CONTROL SHEETS FOR DETAILS FOR WORK BETWEEN RIVER BANKS.  
 ADJUST PERIMETER EROSION BARRIER ALONG RIVER AS NEEDED FOR ACCESS TO CAUSEWAY, TEMPORARY BRIDGE AND CONSTRUCTION OF PIER.

PLOT SCALE: 1"=20'  
 FILE NAME: ...\\prpln-abc-sht-RedGate-es-24.dgn  
 USER NAME: tblank  
 PLOT DATE: 1/4/2012

FILE NAME =	DESIGNED - MAC	REVISED - ADDENDUM 1-6-12
...\\prpln-abc-sht-RedGate-es-24.dgn	DRAWN - TMB	REVISED -
USER NAME = tblank	CHECKED - RMT	REVISED -
PLOT DATE = 1/4/2012	DATE - 10/23/2011	REVISED -



CITY OF ST. CHARLES

EROSION AND SEDIMENT CONTROL RED GATE ROAD		F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			04-00092-00-BR	KANE	440	110
SCALE: 1"=20'		SHEET NO. 9 OF 23 SHEETS		STA. 110+00.00 TO STA. 116+00.00		CONTRACT NO. 63650
ILLINOIS FED. AID PROJECT						