

- SPECIALITY ITEM
- NON-PARTICIPATING ITEM
- 100% WINNEBAGO COUNTY COST

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODES								
				I-90 CONSTRUCTION 90% FEDERAL 10% STATE 0003	BRIDGE SN. 101-0193 90% FEDERAL 10% STATE 0010	BRIDGE SN. 101-0194 90% FEDERAL 10% STATE 0010	BOX CULVERT SN. 101-1095 90% FEDERAL 10% STATE 0010	ROCKTON @ WB I-90 SIGNALS 90% FEDERAL 3.34% STATE 6.66% WINNEBAGO COUNTY 0021	ROCKTON @ EB I-90 SIGNALS 90% FEDERAL 3.34% ISTHA 6.66% WINNEBAGO COUNTY 0021	ISTHA SIGNS 100% ISTHA 0021	WISDOT DMS SIGN 100% WISCONSIN DOT 0021	
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1445	1445								
42000316	PORTLAND CEMENT CONCRETE PAVEMENT 8 3/4" (JOINTED)	SQ YD	224	224								
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	8267	8267								
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	1790	1790								
42000541	PORTLAND CEMENT CONCRETE PAVEMENT 12" (JOINTED)	SQ YD	153	153								
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	3065	3065								
42100355	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 12 3/4"	SQ YD	117258	117258								
42100615	PAVEMENT REINFORCEMENT	SQ YD	117258	117258								
42101300	PROTECTIVE COAT	SQ YD	120549	120549								
44000100	PAVEMENT REMOVAL	SQ YD	147996	147996								
44000155	HOT-MIX ASPHALT SURFACE REMOVAL	SQ YD	1609	1609								
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	591	591								
44003100	MEDIAN REMOVAL	SQ FT	2544	2544								
44004000	PAVED DITCH REMOVAL	FOOT	225	225								
44004250	PAVED SHOULDER REMOVAL	SQ YD	8940	8940								
44213204	TIE BARS 3/4"	EACH	56096	56096								
48100100	AGGREGATE SHOULDERS, TYPE A	TON	614	614								
48101200	AGGREGATE SHOULDERS, TYPE B	TON	808	808								
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	243	243								
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1197	1197								
48300100	PORTLAND CEMENT CONCRETE SHOULDERS 6"	SQ YD	1160	1160								
48300415	PORTLAND CEMENT CONCRETE SHOULDERS 9 3/4"	SQ YD	5103	5103								
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	1422	1422								
48300715	PORTLAND CEMENT CONCRETE SHOULDERS 12 3/4"	SQ YD	60889	60889								
48301000	PROTECTIVE COAT	SQ YD	64184	64184								
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	3	3		1	1	1				
50104400	CONCRETE HEADWALL REMOVAL	EACH	8	8								
50105220	PIPE CULVERT REMOVAL	FOOT	2418	2418								
50200100	STRUCTURE EXCAVATION	CU YD	360	360		189	171					
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	714.5	714.5				714.5				
50300225	CONCRETE STRUCTURES	CU YD	491	25	247	219						
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1111.8		587.3	524.5						
50300260	BRIDGE DECK GROOVING	SQ YD	2159		1145	1014						
50300280	CONCRETE ENCASMENT	CU YD	25.6		13.6	12						
50300300	PROTECTIVE COAT	SQ YD	2446		1289	1157						
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1							
50500505	STUD SHEAR CONNECTORS	EACH	12597		6669	5928						
50800105	REINFORCEMENT BARS	POUND	17960	17960								
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	344,145	11380	166795	148410			12,010		5550	
50800515	BAR SPLICERS	EACH	282		150	132						
51200958	FURNISHING METAL SHELL PILES 14" X 0.250"	FOOT	6490		3450	3040						
51202305	DRIVING PILES	FOOT	6490		3450	3040						
51203200	TEST PILE METAL SHELLS	EACH	4		2	2						
51500100	NAME PLATES	EACH	3		1	1	1					



USER NAME = .USERNAME.	DESIGNED -	REVISED -
FILE NAME = #FILE#	DRAWN - KRL	REVISED -
PLOT SCALE = 5/8" = 1' / IN.	CHECKED - PDS	REVISED -
PLOT DATE = 11/15/2011	DATE - 10-21-2011	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: N/A	SHEET NO. OF SHEETS	STA. TO STA.	

F.A. RTE. 90	SECTION (X2-1) R	COUNTY WINNEBAGO	TOTAL SHEETS 510	SHEET NO. 8
ILLINOIS FED. AID PROJECT			CONTRACT NO. 64C29	

Rev. 1-5-12