

- SPECIALITY ITEM
- NON-PARTICIPATING ITEM
- 100% WINNEBAGO COUNTY COST

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODES							ISTHA SIGNS 100% ISTHA 0021	WISDOT DMS SIGN 100% WISCONSIN DOT 0021
				I-90 CONSTRUCTION 90% FEDERAL 10% STATE 0003	BRIDGE SN. 101-0193 90% FEDERAL 10% STATE 0010	BRIDGE SN. 101-0194 90% FEDERAL 10% STATE 0010	BOX CULVERT SN. 101-1095 90% FEDERAL 10% STATE 0040	ROCKTON @ WB I-90 SIGNALS 90% FEDERAL 3.34% STATE 6.66% WINNEBAGO COUNTY 0021	ROCKTON @ EB I-90 SIGNALS 90% FEDERAL 3.34% ISTHA 6.66% WINNEBAGO COUNTY 0021			
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1								
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	1								
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	1								
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	200	200								
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	36	36								
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1								
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	279879	279879								
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2750	2750								
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	87918	87918								
70400100	TEMPORARY CONCRETE BARRIER	FOOT	34452	34452								
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	101841	101841								
70500615	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	2	2								
72000100	SIGN PANEL - TYPE 1	SO FT	169	169								
72000200	SIGN PANEL - TYPE 2	SO FT	461	461								
72000300	SIGN PANEL - TYPE 3	SO FT	5163	5163								
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	32	32								
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	31	31								
72400320	REMOVE SIGN PANEL - TYPE 2	SO FT	16	16								
72400330	REMOVE SIGN PANEL - TYPE 3	SO FT	5163	5163								
72600100	MILE POST MARKER ASSEMBLY	EACH	22	22								
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	34840	34840								
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	156	156								
72900200	METAL POST - TYPE B	FOOT	34	34								
73000100	WOOD SIGN SUPPORT	FOOT	548	548								
73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	10	10								
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	120	120								
73300300	OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (5'-0" X 7'-0")	FOOT	100									100
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	87	67								20
73301840	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	22	22								
73302210	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (36" X 7'-0")	FOOT	35	35								
73400100	CONCRETE FOUNDATIONS	CU YD	73.9	73.9								
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	125.7	59						32.5		34.2
73500100	RELOCATE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1	1								
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1	1								
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1	1								
73602000	REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	EACH	2							2		
73700100	REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	58	58								
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	52	52								
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	4	4								
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	63378	63378								
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	17451	17451								
78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	16910	16910								
78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	2658	2658								
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1699	1699								



USER NAME = .USERNAME.
 FILE NAME = #FILE#
 PLOT SCALE = 50.0000' / 1" IN.
 PLOT DATE = 11/15/2011

DESIGNED -
 DRAWN - KRL
 CHECKED - PDS
 DATE - 10-21-2011

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE. 90	SECTION (X2-1) R	COUNTY WINNEBAGO	TOTAL SHEETS 510	SHEET NO. 11
ILLINOIS FED. AID PROJECT			CONTRACT NO. 64C29	

Rev. 1-5-12