

- SPECIALITY ITEM
- NON-PARTICIPATING ITEM
- 100% WINNEBAGO COUNTY COST

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODES								
				I-90 CONSTRUCTION 90% FEDERAL 10% STATE 0003	BRIDGE SN. 101-0193 90% FEDERAL 10% STATE 0010	BRIDGE SN. 101-0194 90% FEDERAL 10% STATE 0010	BOX CULVERT SN. 101-1095 90% FEDERAL 10% STATE 0010	ROCKTON @ WB I-90 SIGNALS 90% FEDERAL 3.34% STATE 6.66% WINNEBAGO COUNTY 0021	ROCKTON @ EB I-90 SIGNALS 90% FEDERAL 3.34% ISTHA 6.66% WINNEBAGO COUNTY 0021	ISTHA SIGNS 100% ISTHA 0021	WISDOT DMS SIGN 100% WISCONSIN DOT 0021	
78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	323	323								
78200410	GUARDRAIL MARKERS, TYPE A	EACH	121	121								
78200530	BARRIER WALL MARKERS, TYPE C	EACH	3114	3114								
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	7	7								
78300100	PAVEMENT MARKING REMOVAL	SQ FT	36950	36950								
80300100	LOCATING UNDERGROUND CABLE	FOOT	4755	4755								
80500100	SERVICE INSTALLATION, TYPE A	EACH	2					1	1			
81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	495	285						210		
81028750	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2" DIA.	FOOT	188					169	19			
81028760	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2 1/2" DIA.	FOOT	342					161	181			
81028770	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 3" DIA.	FOOT	145					42	103			
81028790	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 4" DIA.	FOOT	530					262	268			
81200270	CONDUIT EMBEDDED IN STRUCTURE, 4" DIA., PVC	FOOT	374	374								
81400100	HANDHOLE	EACH	9	2				4	3			
81400300	DOUBLE HANDHOLE	EACH	2					1	1			
81603025	UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.4 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	1259	1259								
81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	2576	2576								
81603065	UNIT DUCT, 600V, 2-1C NO.2, 1/C NO.2 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	2315	2315								
81603095	UNIT DUCT, 600V, 4-1C NO.2, 1/C NO.4 GROUND, (XLP-TYPE USE), 1 1/2" DIA. POLYETHYLENE	FOOT	904	904								
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	1825					810	1015			
81800190	AERIAL CABLE, 2-1/C NO. 2 WITH MESSENGER WIRE	FOOT	265	265								
81800400	AERIAL CABLE, 4-1/C NO. 2 WITH MESSENGER WIRE	FOOT	385	385								
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	2	2								
82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 250 WATT	EACH	4					2	2			
82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	26	26								
82104000	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 400 WATT	EACH	4	4								
82500330	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240VOLT, 60AMP	EACH	1	1								
83062540	LIGHT POLE, WEATHERING STEEL, 45 FT. M.H., 15 FT. MAST ARM	EACH	2	2								
83062730	LIGHT POLE, WEATHERING STEEL, 45 FT. M.H., TENON MOUNT	EACH	30	30								
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	195	195								
83800650	BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN	EACH	120	120								
84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	61	61								
84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	20	20								
84200804	REMOVAL OF POLE FOUNDATION	EACH	20	20								
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	1	1								
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1	1								
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2					1	1			
86200200	UNINTERRUPTIBLE POWER SUPPLY, STANDARD	EACH	2					1	1			
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3090					1645	1445			
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1545					490	1055			
87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 3C	FOOT	224					187	37			
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	2055					1290	765			
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	5					3	2			



USER NAME = USERNAME
 FILE NAME = #FILE#
 PLOT SCALE = 50.0000' / 1" IN.
 PLOT DATE = 11/15/2011
 DESIGNED -
 DRAWN - KRL
 CHECKED - PDS
 DATE - 10-21-2011
 REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE. 90	SECTION (X2-1) R	COUNTY WINNEBAGO	TOTAL SHEETS 510	SHEET NO. 12
CONTRACT NO. 64C29			[ILLINOIS] FED. AID PROJECT	

Rev. 1-5-12