

## EROSION CONTROL SCHEDULE - CONTINUED

				25000750	25100630	25100900	28000250	28000305	28000400	28000500	28001000	28100105	28100109	28200200	28200200
				MOWING	EROSION CONTROL BLANKET	TURF REINFORCEMENT MAT	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	AGGREGATE (EROSION CONTROL)	STONE RIPRAP, CLASS A3	STONE RIPRAP, CLASS A5	FILTER FABRIC	FILTER FABRIC INLET PROTECTION
STATION	OFF	STATION	OFF	ACRE	SO YD	SO YD	POUND	FOOT	FOOT	EACH	TON	SO YD	SO YD	SO YD	EACH
127+77	-														
127+80	RT							14							
129+50	LT							14							
130+14	-									1					
130+80	RT							14							
132+46	RT	132+61	RT			38				1					
133+46	RT							14							
134+39	LT							14							
134+87	LT									1					
135+00	RT	136+32	RT						164						
135+00	LT	307+00	LT	0.31											
135+25	RT	136+63	RT						148						
135+46	LT	137+37	LT						198						
136+00	RT							14							
136+38	RT	141+50	RT		1857										
136+44	LT	136+80	LT			55									
136+44	RT									1					
136+68	RT							21							
136+77	LT									1					
136+78	RT	142+66	RT						684						
136+87	RT	137+17	RT			50									
136+96	LT							14							
137+00	RT							14							
137+03	LT	142+46	LT						603						
137+21	LT	137+44	LT			37									
137+43	RT	137+71	RT								56				
137+45	LT							21							
137+53	LT	142+50	LT						637						
137+77	RT							14							
138+52	RT							14							
139+40	RT							14							
139+60	RT							28							
139+92	LT	140+05	LT								11				
140+39	RT	142+30	RT						203						
140+43	RT							14							
141+28	RT							28							
143+01	LT								233						
143+22	RT								316						
145+93															1
148+93															1
307+00	LT	ROCKTON RD	LT	3.15											
411+00	RT	ROCKTON RD	RT	3.89											
983+05	LT/RT								48						
983+06	LT/RT	988+85	LT/RT		2807										
989+10	LT/RT	999+81	LT/RT		4871										
980+37.00	LT									1					
985+50.00	-									1					
996+75.00	-							14							
996+80.00	-									1					
DRY CREEK															
15+00		15+74.10	RT			116.8									
15+00.00		16+00	RT										162.3		162.3
17+33.9		18+64.10	RT										403.5		403.5
18+64.10		19+00	RT			49.6									
15+00		16+00	LT										317.0		317.0
17+33.89		18+60.12	LT										245.4		245.4
17+75		18+64.10	LT			133.5									
18+64.10		19+00	LT			44.6									
TOTAL				43.76	30841	2533.5	27255	1967	37232	72	67	40	1128.2	1168.2	2



USER NAME = USERNAME  
 FILE NAME = \*FILE\*  
 PLOT SCALE = 50,0000' / IN.  
 PLOT DATE = 12/12/2011

DESIGNED -  
 DRAWN - KRL  
 CHECKED - PDS  
 DATE - 10-21-2011

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: N/A    SHEET NO.    OF    SHEETS    STA.    TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	(X2-1) R	WINNEBAGO	510	41
CONTRACT NO. 64C29				
ILLINOIS FED. AID PROJECT				

Rev. 1-9-12