

LANDSCAPING SCHEDULE - CONTINUED

				2101615	25000210	25000310	X0322352	25000400	25000500	25000600	25100115	20100110	20100210	20100500
				TOPSOIL FURNISH AND PLACE, 4" SO YD	SEEDING, CLASS 2A ACRE	SEEDING, CLASS 4 ACRE	SEEDING MOBILIZATION EACH	NITROGEN FERTILIZER NUTRIENT POUND	PHOSPHORUS FERTILIZER NUTRIENT POUND	POTASSIUM FERTILIZER NUTRIENT POUND	MULCH, METHOD 2 ACRE	TREE REMOVAL (6 TO 15 UNITS DIAMETER) UNIT	TREE REMOVAL (OVER 15 UNITS DIAMETER) UNIT	TREE REMOVAL, ACRES
STATION	OFF	STATION	OFF											
DRY CREEK														
15+00		15+74.10	RT			0.02								
18+64.10		19+00	RT			0.01								
17+70		18+60.12	LT			0.03								
18+64.10		19+00	LT			0.01								
TOLLWAY DETENTION														
136+00	RT	141+50	RT	882										
RAMPS														
300+26.53	65' RT											7		
300+27.90	60' RT											8		
300+40.86	45' RT											8		
300+40.82	48' RT											8		
300+41.44	44' RT											8		
300+41.86	62' RT											8		
300+58.21	54' RT											10		
412+86.95	21' RT											8		
412+92.94	17' RT											8		
413+24.74	9' RT											8		
416+98.50	30' RT											13		
417+00.85	35' RT											6		
417+16.64	44' RT											7		
419+70.72	65' LT											6		
300+61.25	38' RT												23	
300+63.54	42' RT												18	
300+65.24	39' RT												18	
300+67.40	45' RT												17	
412+43.75	5' RT												24	
412+59.05	21' RT												27	
412+85.57	25' RT												21	
413+85.56	8' RT												25	
414+35.03	15' RT												24	
415+26.24	16' RT												22	
304+03.79	RT	307+81.36												0.2
983+06	LT/RT	142+66	LT/RT				13							
983+06	LT/RT	988+85	LT/RT		0.58									
989+10	LT/RT	999+81	LT/RT		1.01									
IL 75 Ramp C				741										
IL 75 Ramp B				708										
I-90 EXIT RAMP TO VISITOR CENTER														
7+99.40		11+00.00		387										
I-90 ENTRANCE RAMP FROM VISITOR CENTER														
37+00.00		37+31.08		45										
ROCKTON ROAD														
Rockton Rd, NE Ramp				3432										
Rockton Rd, NW Ramp				3693										
5002+06.77	RT	5005+11.21	RT	347										
5008+65.27	LT	5009+66.57	LT	246										
SW corner WB Rockton Rd Exit				92										
SE corner WB Rockton Rd Exit				177										
TOTAL				12823	30.2	5.87	13	2578.4	2578.4	2578.4	29.64	113	219	0.2



USER NAME = _USERNAME_
 FILE NAME = #FILE#
 PLOT SCALE = 50.0000' / IN.
 PLOT DATE = 12/12/2011

DESIGNED -
 DRAWN - KRL
 CHECKED - PDS
 DATE - 10-21-2011

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N/A SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	(X2-1) R	WINNEBAGO	510	43
CONTRACT NO. 64C29			ILLINOIS FED. AID PROJECT	

Rev. 1-9-12