


- NOTES:**
- EXISTING OVERHEAD SIGN STRUCTURE TO BE REMOVED DURING PRE-STAGE.
 - TEMPORARY BRIDGE MOUNTED SIGN TO BE RELOCATED FROM STAGE 1/WINTER SHUT DOWN LOCATION.
 - THE EXISTING SIGN CONTROLLER AND NEW INDUCTION LUMINAIRES SHALL BE RELOCATED TO THE TEMPORARY LOCATION OF THE SIGN ATTACHED TO THE ROCKTON ROAD BRIDGE DURING CONSTRUCTION OF THIS PROJECT.
 - CONTRACTOR TO INSPECT CONDITION OF CONTROLLER AND NEW INDUCTION LUMINAIRES PRIOR TO REMOVAL FROM EXISTING LOCATION, INSTALLATION ON TEMPORARY BRIDGE MOUNTS, REMOVAL FROM TEMPORARY LOCATIONS AND REINSTALLATION ON NEW SIGN STRUCTURE.
 - REFER TO ISTHA'S STANDARD H-10-00.
 - EXTEND SIGN LIGHTING CONDUCTORS AND CONDUIT TO THE NEW LOCATION OF THE BRIDGE MOUNTED SIGN.

- LEGEND:**
- EXISTING UNIT DUCT
 - - - PROPOSED UNIT DUCT
 - ⊗ EXISTING LIGHT POLE TO REMAIN UNLESS NOTED OTHERWISE
 - ⊠ EXISTING LIGHTING CONTROLLER
 - PROPOSED HANDHOLE
 - TEMPORARY LIGHT POLE
 - TEMPORARY WOOD POLE
 - CONDUIT PUSHED, 4" DIA., PVC SCHEDULE 80 (PAID AS UNDERGROUND CONDUIT, PVC, 4" DIA.)



McClure LOCHNER
Engineering & Architecture, Inc.
CHICAGO, ILLINOIS

RWA
REGISTERED PROFESSIONAL ENGINEER
STATE OF ILLINOIS

QEI
QUISO ENGINEERING INC.

USER NAME = .USERNAME.
DESIGNED - BLM
DRAWN - JPW
CHECKED - BLM
DATE - 10/14/11

PLOT SCALE = 50,0000' / IN.
PLOT DATE = 12/9/2011

REVISI -
REVISI -
REVISI -
REVISI -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**TEMPORARY LIGHTING PLAN
BRIDGE MOUNTED SIGN STRUCTURE STAGE 2**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

Rev. 1-9-12

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	(X2-1R)	WINNEBAGO	510	267
CONTRACT NO. 64C29				

ILLINOIS FED. AID PROJECT